

21-34-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company—MAGNOLIA PETROLEUM CO.
Farm—C. Olson "C" No. 1

SEC. 21 T. 34 R. 12W
 SW NE SW

Total Depth. 4793
Comm. 1-21-56 Comp. 3-11-56
Shot or Treated.
Contractor. Graham-Messman-Rinehart Oil Co.
Issued. 8-18-56

County Barber
 KANSAS



CASING:

9 5/8 @ 353' w/ 300 sx cmt.
5 1/2 @ 4792' w/ 150 sx cmt.

Elevation. 1456 DF

Production. 5,300,000 CFGPD

Figures Indicate Bottom of Formations.

clay, shale & gypsum	251
shale	945
shale & anhydrite	1415
lime & shale	3087
shale & sand	3330
lime & shale	3551
shale, sand & lime	3795
shale & lime	4164
lime	4697
Mississippi	4725
Mississippi lime & chert	4760
chert	4772
lime	4793
Total Depth	

TOPS:

Lansing	3994
Kansas City	4302
Mississippian	4697

DST #1: 4700-25, open 1 hr. fr. bl.
faint odor gas IP, rec. 30' SOCM,
FP 15-15#, BHP 530#/20 min.

DST #2: 4725-60, open 1½ hrs. good bl.
thruout, rec. 50' mud, FP 15-15#,
BHP 785#/30 min.