

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


29-34-12W

Company- THE ATLANTIC REFINING CO.
Farm- Edd Sterling "B" No. 1

SEC. 29 T. 34 R. 12W
C NE SW NW

Total Depth. 4843 PBTB 4835
Comm. 6-22-55 Comp. 7-11-55
Shot or Treated.
Contractor. Corbett Drilling Co.
Issued. 10-1-55

County Barber
KANSAS



Elevation. 1518 DF

Production. 4,000,000 CFGPD

CASING:
8 5/8 C 252.57' w/ 250 sx cmt.
1 1/2 C 4842.94' w/ 350 sx cmt.

Figures indicate Bottom of Formations.

sand, shale & red bed	270
shale	576
shale & red bed	1085
sand & shale	1503
shale & lime	1915
lime	2105
lime & shale	2898
lime	2965
shale & lime	3150
lime	3325
lime & shale	3615
sand & shale	3755
shale & lime	3780
sandy shale & lime	3840
sandy lime & shale	3901
lime & shale	4061
sand & lime	4143
lime	4310
lime & shale	4441
lime	4603
lime & shale	4677
lime	4710
lime & shale	4748
coring	4802
colomite	4843

Total Depth Plug back to 4835:

SCOUT TOPS:

Elgin	3622
Heebner	3838
Toronto	3866
Borlord	3942
Brown lime	4056
Lansing	4062
Kansas City	4355
Conglomerate	4748
Mississippi	4783

Perf. 4764-74, 4796-4808, 4788-96,
Schlumberger Meas. w/ 4 JSPF