

32-34-12W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SUN OIL CO.
Farm- Graves

No. 1

SEC. 32 T. 34 R. 12W
SE NW NE

Total Depth. 4807

Comm. 8-2-55

Shot or Treated.


Contractor.

Issued. 11-5-55

Comp. 8-19-55

County Barber

KANSAS



CASING:

8 5/8 @ 320' w/ 275 sx cmt.

5 1/2 @ 4807' w/ 150 sx cmt.

Elevation. 1472 DF

Production. 3,162,000 CFGPD

Figures indicate Bottom of Formations.

surface clay & sand	100
shale & red bed	660
shale	995
limey shale	1230
broken lime & shale	1942
limey shale	2090
lime & shale	2969
lime & shaley lime	3405
limey shale	3794
lime w/ shale streaks	3904
shale	4073
lime & shale	4103
Lansing lime	4250
limey shale	4298
lime	4554
lime w/ shale streaks	4765
Mississippi lime	4807
Total Depth	

SCOUT TOPS:

Heebner	3842
Lansing	4103
Kansas City	4118
Mississippi	4765

Cored 4768-4807, rec. 38'

Perf. 4 SPF 4765-80