

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


33-34-12W

Company- ATLANTIC REFG. CO.
Farm- J. LeRoy Graves No. 2
G.U.

SEC. 33 T. 34 R. 12W
C NW NE

Total Depth. 4845'
Comm. 12-6-56 Comp. 12-22-56
Shot or Treated.
Contractor. Musgrove Petro. Corp.
Issued. 3-23-57

County Barber
KANSAS



CASING:

8 5/8" 210' 47' W/175 sx cem
5 1/2" 4845' W/200 sx cem.

Elevation. 1432' DF

Production. 17,800,000 CF/GPD

Figures indicate Bottom of Formations.

clay-red bed	60
shells-red bed	215
shale	915
shale-lime strks	1380
shale-lime	3640
sand-shale-lime	3765
sand-shale	3816
lime-shale	4398
lime	4700
lime-sand	4725
sand	4740
sand-cherty dolomite	4780
cherty lime	4845
Total Depth	

TOPS: Scout
Heebner 3805
Lansing 4113
Cherokee 4698
Mississippi conglom-
erate 4722
Mississippi Dolomite 4745

DST #1 4704-25 (Cherokee)
Packer failed in 2 min.

DST #2 4679-4725 (Cherokee): 1 hr. 10 min.
TO 1 hr., gas to surface in
20 min. @ rate of 310 MCF/D.
Rec. 210' GCM. I&FFP 65#.
BHSIP 1765#/30 min.

DST #3 4723-80 (Miss.): TO
1 hr., gas to surface in 16
min. @ rate of 165 MCF/D.
Rec. 110' GCM. IFP 145#, FFP 165#.
IBHSIP 1970#/30 min. FBHSIP 1820"
30 min.

Perf. 4700-04' & 4713041'
Sandfraced w/30,000 gals.