

Company. SKELLY OIL CO.
Farm. R. H. Donovan No. 1


SEC. 1 T. 34 R. 13W

NW SE SW

990' fr EL, 990' fr SL, SW/4

County Barber

KANSAS



Total Depth. 4780 PBD 4746
Comm. 2-5-56 Comp. 2-22-56
Shot or Treated. 250 gal acid 4718-33: Vis-O-Frac 4718-33 &
Contractor. Chas. Hulme Drilling Co., Inc. 4690-4712
Issued. 5-5-56

8 5/8 @ CASING; 418' w/ 250 sx cmt.
5 1/2 @ 4780' w/ 200 sx cmt.

Elevation. 1585 DF

Production. 4,977,000 CFGPD

Figures Indicate Bottom of Formations.

surface soil & clay	100
clay & shells	418
shale & shells	1100
shale & lime	1685
shale	1710
lime	2020
lime & shale	2080
lime	2475
shale & lime	2760
shale	3135
lime & shale	3480
shale	3550
shale & sand	3820
lime & shale	4000
lime	4690
white tripolitic & white clear translucent chert	4720
white opaque & tripolitic chert	4750
lime	4780
Total Depth	

Plugged back to 4746

TOPS:

Elgin sand	3620
Heebner	3829
Lansing	4023
Base K. C.	4546
Marmaton lime	4560
Mississippi lime	4688

Perf. 131/4690-4712, 90/4718-33

Producing Formation: Mississippi
lime 4690-4712 & 4718-33.

DST #1: packer @ 4680, 40' anchor,
open 1 hr. good bl. air immed. gas to
surf. 4 min. too small to meas. rec.
55' drlg. mud, IFP 35#, FFP 42#,
BHP 1614#/20 min.

DST #2: packer @ 4720, 30' anchor,
open 1 hr. gas to surf. 2 min. ga.
1700 MCFGPD, rec. 45' drlg. mud,
IFP 225#, FFP 225#, BHP 1625#/20 min.

Ran Schlumberger Survey