

508 East Murdock,

Wichita, Kansas

5-34-13W

Company- IMPERIAL OIL OF KANSAS, INC.
 Farm- Blunk "C" No. 1

SEC. 5 T. 34 R. 13W
 NE SE NW

Total Depth. 4976'

Comm. 4-2-56

Comp. 4-24-56


County Barber

KANSAS

Shot or Treated.

Contractor. Patton Drlg. Co.

Issued. 6-16-56



CASING:

13" 237' cem w/250 sx

Elevation. 1876'

Production. Dry

Figures indicate Bottom of Formations.

surface sand & gravel	103
red beds shells	225
red beds gyp shells	260
red beds & shells	800
shale & shells	1550
salt & shale	1600
lime & shale	2055
anhydrite & shale	2164
lime & shale	3297
shale	3385
lime & shale	3665
lime	3765
lime & shale	3940
sandy shale	4025
sand & sandy shale	4034
lime & shale	4158
lime	4196
lime & shale	4215
sand & sandy shale	4274
lime & shale	4429
lime	4471
lime & shale	4542
lime	4567
lime & shale	4764
lime	4808
lime & shale	4898
lime	4976
Total Depth	

11' from kelly bushing to ground level.

Tops:

Heebner	4110
Douglas Sand	4198
Lansing	4310
Mississippi	4870

DST #1 4170-4274', open 1 hr., rec. 30'
 mud. No oil or gas. FP 28#-40# BHP 860#.

DST #2 4871-4900', open 1 hr., rec. 45'
 mud. FP 30#-45# BHP 170#.

DST #3 4863-4976', open 1 hr., rec. 250'
 mud. BHP 160#.