

15-007-20580
 DEC 8-34 13W

IMPORTANT
 Kans. Geo. Survey request
 samples on this well.

Geological Survey
WICHITA DRILLERS LOG


API No. 15 — 007 — 20,580
 County Number

S. 8 T. 34 R. 13 ^W
 Loc. 250' W/C W2 NW NW

Operator
 George R. Jones

County Barber

Address
 1310 - 125 N. Market Wichita, Kansas 67202



Well No. #3 Lease Name Blunk Blunk

Footage Location
 feet from (N) (S) line feet from (E) (W) line

Principal Contractor Gabbert-Jones, Inc. Geologist Lee Poulsen

Spud Date December 21, 1977 Total Depth 5360' P.B.T.D. --

Elev.: Gr. _____

Date Completed January 6, 1978 Oil Purchaser --

DF 1831 KB 1834

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

| Purpose of string | Size hole drilled | Size casing set (in O.D.) | Weight lbs/ft. | Setting depth | Type cement | Sacks | Type and percent additives |
|-------------------|-------------------|---------------------------|----------------|---------------|-------------|-------|----------------------------|
| Surface | 13" | 8 5/8" | 28 | 372 | Common | 300 | 3% CC |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

LINER RECORD

PERFORATION RECORD

| Top, ft. | Bottom, ft. | Sacks cement | Shots per ft. | Size & type | Depth interval |
|----------|-------------|--------------|---------------|-------------|----------------|
| None | | | None | | |
| | | | | | |
| | | | | | |

TUBING RECORD

| Size | Setting depth | Packer set at |
|------|---------------|---------------|
| None | | |
| | | |
| | | |

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

| Amount and kind of material used | Depth interval treated |
|----------------------------------|------------------------|
| None | |
| | |
| | |

INITIAL PRODUCTION

| | | | | | |
|--|---|-----|------------------------|---------------|--|
| Date of first production None | Producing method (flowing, pumping, gas lift, etc.) | | | | |
| RATE OF PRODUCTION PER 24 HOURS | Oil | Gas | Water | Gas-oil ratio | |
| | bbls. | MCF | bbls. | CFPB | |
| Disposition of gas (vented, used on lease or sold) | | | Producing interval (s) | | |

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

GEORGE R. JONES

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
DRY HOLE

Well No.

3

Lease Name

Blunk

S 8 T 34S R 13 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

| FORMATION DESCRIPTION, CONTENTS, ETC. | TOP | BOTTOM | NAME | DEPTH |
|--|-----|--------|--|--|
| DST #1: 4842-4900'. 30-30-60-60. Weak blow thruout. Rec. 170' mud. IFP 69-119# FFP 139-159# ICIP 208 PSI FCIP 287 PSI | | | Sample Tops: Mississippi Viola Simpson Sh Simpson SS | 4840 (-3006') 5202 (-3368') 5322 (-3488) 5335 (-3501) |
| DST #2: 5312-41'. 30-60". Very weak blow, died 20", Rec 20' mud. FP 20 - 20# BHP 825 PSI | | | No log run. | |
| DST #3: 5336-60'. 30-60". Very weak blow; died in 15". Rec 20' mud. FP 20 - 20# BHP 1005 PSI | | | | |

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

George R. Jones
Signature

Owner

Title

January 18, 1978

Date

3-30-13 m

8-34-13W

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Blunk #3
C-W/2-NW-NW Sec 8-34S-13W
Barber County Kansas

Commenced: 12-21-77

Completed: 1-6-78


OPERATOR: GEORGE R. JONES

| Depth | | Formation | Remarks |
|-------|-----------|-----------------|--|
| From | to | | |
| 0 | 20 | Sand | Ran 9 jts of 20# 8 5/8" csg set @ 362' Cemented w/ 300 sks Common 3% CC PD @ 3:50 a.m. 12-22-77 |
| 20 | 340 | Red Rock-Redbed | |
| 340 | 368 | Shells-Clay | |
| 368 | 1080 | Shale-Shells | |
| 1080 | 2120 | Shale | |
| 2120 | 2182 | Lime-Shale | |
| 2182 | 2543 | Shale-Lime | |
| 2545 | 2745 | Lime | |
| 2745 | 3135 | Lime-Shale | |
| 3135 | 3487 | Lime | |
| 3487 | 3675 | Lime-Shale | |
| 3675 | 5360 - TD | Lime | DRY & ABANDONED |

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.


JAMES S. SUTTON II

Subscribed and sworn to before me this 17th day of January, 1978.


ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.