

11-34-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING CO.
Farm- Donovan "D" No. 1

SEC. 11 T. 34 R. 13W
C SW SE

Total Depth. 5308'
Comm. 5-10-63 Comp. 5-28-63
Shot or Treated.
Contractor.
Issued. 9-14-63

County Barber
KANSAS



Elevation. 1584' KB

CASING:
8 5/8" 251' cem w/250 sx.

Production. Dry

Figures indicate Bottom of Formations.

sand & redbed	100
redbed	250
shale & shells	1465
shale & lime	1855
shale & shells	2045
lime & shale	2475
lime & shale strks.	2620
lime & shale	4020
lime	4540
lime & shale	4750
lime	4990
lime & shale	5052
lime	5150
lime & shale	5190
lime & sand	5195
lime	5308
Total Depth	

TOPS: LOG	
Elgin Zone	3648
Elgin Sandstone	3758
Heebner	3861
Douglas	3883
Lansing-Kansas City	4058
Base Kansas City	4553
Mississippi	4692
Kinderhook	4918
Chattanooga	4980
Viola	5032
Simpson Shale	5135
Simpson Sandstone	5146
Lower Simpson Sand	5268

DST #1 4791-4836 Op 70" Rec. 250' wtry
mud, 240' wtr. IBHP 2096#/30"-FBHP
1973#/30", FP 52#-250#.