

12-34-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. ATLANTIC REFINING COMPANY
Farm. V. L. Cook "B" No. 1

SEC. 12 **T.** 34 **R.** 13W
 90' N of Center of
 SW NE SE

Total Depth. 4913' **PBTD** 4878'
Comm. 4-16-56 **Comp.** 5-9-56
Shot or Treated.
Contractor. Iron Drilling Company
Issued. 11-17-56

County Barber
KANSAS



1599' DF

Elevation. _____

Production. 28,700,000 CFGPD

CASING:

8 5/8" @252' w/200 sx cem
 5 1/2" @4912' w/300 sx cem.
 5 1/2" w/4 1/2" hole @4800' figures from Bottom of Formations.
 w/200 sx cem.

surface clay	40
sand & shale	258
shale & shells	1690
shale & lime	1785
lime	1930
shale & lime	2150
lime	2250
lime & shale	3485
lime	3535
sand & shale	3630
shale	3890
lime & shale	4195
lime	4565
lime & shale	4595
lime	4725
lime & shale	4785
lime	4913
Total Depth	
PBTD	4878

SCOUT TOPS

Elgin	3709
Heebner	3909
Toronto	3937
Douglas	3992
Lansing	4119
Kansas City	4360
Cherok	4757
Mississippi	4781

Perforations 4835-67' (Sch.),
 Mississippian formation. Acidized per-
 forations w/1000 gals. acid. Sandfraced
 w/600 bbls. gelled kerosene & 54 bbls.
 sand.