

17-34-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING COMPANY et al
 Farm- Blunk No. 1

SEC. 17 T. 34 R. 13W
 SW SE SW

Total Depth. 5250
 Comm. 7-21-52 Comp. 8-20-52
 Shot or Treated.
 Contractor. Aylward Drilling Co.
 Issued. 10-25-52

County Barber
 KANSAS



8 5/8" CASING:
 214' cem w/105 sx

Elevation. 1620 DF

Production. dry

Figures Indicate Bottom of Formations.

clay red	40
red bed.	450
red bed & sand	830
red bed & lime strks	1080
red bed & shales	1145
anhy. & shale	1240
shale blue, shells	1330
salt, sand, shale	1790
lime, shale	2080
lime hard sandy	2210
lime, shale	2305
lime	2470
lime, shale	3180
lime	3260
shale blue	3280
lime, shale	3370
shale blue, gray	3415
shale, lime	3815
lime sandy, shale	3870
shale, lime	4100
lime	4145
lime chalky	4190
lime	4507
lime, shale	4625
lime	4710
lime, shale	4710 ?
lime	4810
shale, lime	4820
lime	4858
lime, shale	5073
lime	5074
shale, lime	5111
lime	5125
lime, chert	5152
lime	5166
lime cherty	5191
shale, lime	5208
shale lime hard sand	5230
sand	5250
Total Depth	RTD

10' mud. 0 BHP (re-opened tool three times during test)

Zero - Kelly Bushing, 2' above derrick floor.

Tops:	
Elgin Equivalent	3781
Toronto	3955
Douglas Fm.	4005
Lansing	4096
Mississippian	4678
Kinderhook	4962
Chattanooga	5005
Misener	5057
Sylvan-Maquoketa	5064
Viola	5081
Simpson Fm.	5195

DST 4683-4710 fair steady
 blow, open 1 hr., rec. 10'
 mud, BHP 315# in 15 mins.

DST 5226-32 Weak blow for 1½
 mins, open 35 mins. recovered