

17-34-13W P1
JH

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential.
If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 6006

EXPIRATION DATE 6/84

OPERATOR Molz Oil Company

API NO. 15-007-21,745

ADDRESS R.R. #2, Box 54

COUNTY Barber

Kiowa, Kansas 67070

FIELD Aetna Ext

** CONTACT PERSON Jim Molz

PROD. FORMATION D & A

PHONE 361-296-4558

PURCHASER

LEASE Blunk

ADDRESS

WELL NO. 5

WELL LOCATION App. NW/4 NW/4

DRILLING Sweetman Drilling, Inc. Rig 1

750 Ft. from North Line and

CONTRACTOR

555 Ft. from West Line of

ADDRESS 500 Heritage Park Place

the NW (Qtr.) SEC 17 TWP 34 RGE 13 . W

Wichita, Kansas 67202

PLUGGING Sweetman Drilling, Inc.

WELL PLAT

(Office Use Only)

CONTRACTOR

ADDRESS 500 Heritage Park place

Wichita, Kansas 67202

TOTAL DEPTH 4900

PBTD ----

SPUD DATE 1/30/84

DATE COMPLETED 2/6/84

ELEV: GR 1677 DF 1680 KB 1687

DRILLED WITH (~~WIRE~~) (ROTARY) (~~ACRO~~) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE -----

5			
	17		

KCC ☒
KGS ☒
SWD/REP ☐
PLG. ☐

Amount of surface pipe set and cemented 265' DV Tool Used? NO

THIS AFFIDAVIT APPLIES TO: (Circle ONE) -- Oil, Gas, 'Shut-in Gas, (Dry), Disposal, Injection, Temporarily Abandoned, OWWO. Other -----

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Jim Molz, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.



60-1-18-71

ACO-1 WELL HISTORY

OPERATOR Molz Oil Company LEASE Blunk SEC. 17 TWP. 34 RGE. 13 W

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 5

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Red beds	0	1400		
Anhydrite and shale	1400	2105	Chase GP	2105
Limestone and shale	2105	2975		
Shale and sandstone	2975	3010		
Limestone & Shale	3010	3747		
Sandstone white, clear, No show	3747	3910	Elgin Sand	3747
Limestone & Shale	3910	3964		
Shale, carbonaceous	3964	3967	Heebner Sh.	3964
Shale, limestone, & Sandy limestone	3967	4142		
Limestone, and shale	4142	4612	Kansas City	4142
Shale carbonaceous	4612	4616	Cherokee Sh.	4612
Limestone and shale	4616	4716		
Limestone, shaley, dolomitic cherty streaks of minor porosity and fractures	4716	4900	Mississippi	4716
Slight show of oil				
DST #1 4849-4865 30"-45"-60"-120" WK 310- Rec. 25' Drilling mud IFP 124#-124# ISIP 156#-145# FFP 72#-52# FSIP 332#				
Ran Gt. Guns Open Hole Logs. D & A				

Report of all strings set—surface, intermediate, production, etc.—CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	15"	10 3/4		272' KB	Common	230 sks	2% Jel, 3% CC Cement Circ.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Packer set at			