


19-34-13W

Company- E.H. ADAIR OIL CO.  
Farm- Blunk "B" No. 1

SEC. 19 T. 34 R. 13W  
CS 1/2 SW

Total Depth. 4739'  
Comm. 9-15-59 Comp. 9-27-59  
Shot or Treated.  
Contractor. Graham-Michaelis  
Issued. 12-12-59

County Barber  
KANSAS



Elevation. 1639' KB

Production. 3,000,000 CFG

CASING:

8 5/8" 349' w/275 sx cem.  
5 1/2" 4712' w/125 sx cem.

Figures Indicate Bottom of Formations.

clay	40
red beds, shale	1249
shale, lime	3788
sand	3817
shale	3916
lime, shale	3951
blk shale	3955
lime	3958
shale, lime	4130
lime	4550
blk shale	4553
lime	4584
blk shale	4588
lime	4613
shaley lime	4642
shale	4652
shaley lime	4672
shale	4675
lime	4690
shale	4693
lime	4704
cherty lime	4709
cherty dolomite	4739
Rotary Total Depth	

TOPS:

Elgin sand	3788
Heebner shale	3951
Lansing Kansas City	4130
Mississippi dolomite	4709

DST #1, 4709-39: Gas to surface in 3 min.

Gauged 362,000 CFGPD @ 5 min.  
" 537,000 CFGPD @ 10 min.  
" 630,000 " @ 20 min.  
" 700,000 " @ 25 min.

ISIP= 1840# in 20 min.

FSIP= 1760# in 20 min.

IFP= 220#, FFP= 220#.