


Company- E.H. ADAIR OIL COMPANY
Farm- DeWitt No. 1

SEC. 19 T. 34 R. 13W
C SW SE

19-34-13W

County Barber

KANSAS



Total Depth. 4820'
Comm. 12-31-59 Comp. 1-14-60
Shot or Treated.
Contractor.
Issued. 3-19-60

CASING:

8 5/8" 354' cem. w/240 sx.

Elevation. 1711 KB

Production. Dry

Figures indicate Bottom of Formations.

shale & shells	2107
shale & lime	2240
lime	2549
shale & lime	3600
shale	3784
limey shale	3820
shale	3883
sandy shale	3905
shale	3985
shale & lime	4022
black shale	4026
limey shale	4047
lime	4068
sand	4078
lime	4115
shale	4202
lime	4636
black shale	4638
lime	4664
black shale	4668
lime	4692
shale	4696
lime	4719
shale	4730
shaley lime	4778
shaley, cherty lime	4786
cherty dolomite, good staining	4820
Total Depth	

TOPS:

Elgin Zone	3820
Heebner Shale	4022
Lansing	4202
Mississippi Dolomite	4786

DST #1 4778-4820': Open 75 minutes.
Gas to surface in 30 minutes.

Gauged 340,000 cubic feet at 5 minutes.

Gauged 50,000 cubic feet at 75 minutes.

Recovered 250 feet slightly gas-cut mud. ISIP - 1660# in 20 min.

FSIP - 1710# in 20 min.

IFP - 60#.

FFP - 60#.