

19-34-13W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- SOCONY MOBIL OIL CO.  
Farm- John L. Graves UnitNo. 1

SEC. 19 T. 34 R.13W  
C E/2 NW NW

Total Depth. 4825' PB 4765'  
Comm. 12-27-60 Comp. 1-19-61  
Shot or Treated.  
Contractor. Peel Bros.  
Issued. 4-29-61

County Barber

KANSAS



Elevation. 1637' GL

Production. 1,118,000 CFG

Figures Indicate Bottom of Formations.

red bed	325
red bed & shale	785
shale & shells	1015
red bed	1149
shale & shells	1910
lime	1970
lime, shale streaks	2100
lime	2745
lime & shale	3405
lime	3450
lime & shale	4135
lime	4825
Total Depth	
Plugged back to 4765'	

TOPS: SCHLUMBERGER

Elgin	3770
Heebner	3975
Douglas	4035
Lansing	4150
Mississippian	4731

Acidized OH 4735-65' w/250 gal MCA 7½% acid.  
Flushed w/76 BSW.

Treated OH 4735-65' w/20,000 gal 6% acid &  
20,000# of 20-40 sand. Flushed w/80 BTrSW.