


20. 34-13W

Company- E. H. ADAIR OIL COMPANY
Farm- Hull No. 1

SEC. 20 T. 34 R. 13W
SW SW SE

Total Depth. 4854
Comm. 4-12-56 Comp. 5-5-56
Shot or Treated.
Contractor.
Issued. 7-21-56

County Barber
KANSAS



Elevation. 1655 K.B.

CASING:
8 5/8" 323' cem w/270 sx.
5 1/2" 4796' cem w/100 sx.

Production. D & A

Figures indicate Bottom of Formations.

shale	200
shale, shells	1900
lime, shale	2077
lime	2167
lime, shale	2329
lime	2400
lime, shale	3013
shale	3044
shale, lime	3143
shale	3267
lime, shale	3879
shale	3980
lime, shale	4161
lime	4478
shale	4484
lime	4494
lime oolitic	4502
lime	4614
shale black	4619
lime	4642
shale black	4647
lime	4671
shale black	4674
lime shaley	4719
lime	4729
shale	4733
lime	4753
shale	4755
lime	4781
conglomerate	4789
dolomite	4854
Total Depth	

Tops:

Elgin Zone	3787
Heebner	3995
Toronto (Scout)	4011
Douglas	4064
Lansing-K.C.	4161
Conglomerate(Scout)	4781
Miss. Dolomite	4789

5
Cleaned out to T.D. Frac w/10,000
lbs sand & 10,000 lb diesel fuel.
Tested approx. 300,000 Cu.ft.gas
per day. P & A