

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

29-34-13W


Company- SKELLY OIL COMPANY
Farm- Jacob Roberts No. 1

SEC. 29 T. 34 R. 13W
NE NW NW
330' from NL, 990' from WL
of NW/4

County Barber

Total Depth. 4881'
Comm. 9-25-64 Comp. 12-16-64
Shot or Treated. MISSISSIPPIAN 4840' 68 shots
Contractor. K & E Drlg.
Issued. 3-6-65

KANSAS



Elevation. 1712' KB

Production. 2090 MCFGPD

CASING:

8 5/8" 485' cem w/300 sx
5 1/2" 4881' cem w/100 sx

Figures Indicate Bottom of Formations.

Clay and sand	50
red bed	135
shale and sand	197
shale and shells	1000
shale	1045
shale and shells	1930
lime	2095
lime and shale	2300
lime	3010
lime and shale	3890
lime	4816
cherty dolomite	4855
lime	4881
Total Depth	4881

TOPS: LOG

Heebner	4031
Lansing	4202
Base Kansas City	4708
Mississippian	4816

Ran Welex Forxo Log, Acoustic Velocity Log & Gamma-Guard Log from 4881' to surface.