

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


30-34-134

Company- E. H. ADAIR OIL CO.
Farm- Sutton No. 1

SEC. 30 T. 34 R. 13W
C NE SW

Total Depth. 4820'
Comm. 12-9-58 Comp. 12-24-58
Shot or Treated.
Contractor. Bachus Oil Co
Issued. 2-14-59

County Barber
KANSAS



CASING:
8 5/8" 306' cem w/250 sx.

Elevation. 1653' KB

Production. Dry

Figures indicate Bottom of Formations.

red rock & gyp 40
sand 50
redbeds & shale 1150
shale & lime 1340
shale & Anhydrite 1855
lime 2190
lime & shale 3400
lime 3438
shale 3454
lime 3465
limey shale 3513
shale 3765
shaley lime 3790
shale & sandy shale 3873
sand 3893
shale 3962
shaley lime 3999
black shale 4001
lime 4060
shaley lime 4086
shale 4175
lime 4184
porous lime 4189
lime 4365
porous lime 4369
lime 4599
black shale 4601
lime 4617
black shale 4622
lime 4648
shale, black 4652
lime 4676
shale 4679
lime 4701
shaley lime 4714
lime 4728
shale 4731
lime 4754
shale 4757
lime 4769
shale 4773
Conglomerate 4786
cherty dolomite, show
of gas 4820
Total Depth

DST #1 4788-4805, op 1 hr., w/a fair
blow thruout test. Rec. approx. 4800'
of gas in drill pipe and 186' gas-cut
mud. ISIP 1840#/20 mins. FSIP 1720#/20 mins.
IFP 0, FFP 130#.

DST #2 4789-4820, op 1 hr., gas to surface in
16 min, not enough to gauge. Rec. 90' gas-cut
mud. ISIP 1620#/20 min. FSIP 1360#/20 min.
IFP 0, FFP 0.

TOPS:
Elgin Zone 3790
Elgin Sand 3873
Heebner Shale 3999
Douglas Shale 4060
Lansing-Kansas City 4175
Mississippi Dolomite 4786