



LOCATION 6-34-13  
FIELD Wildcat  
COUNTY Barber  
STATE Kansas  
CONTRACTOR Deek Drilling  
Company

Date March 5, 1952  
Ticket No. 6347-T  
HOWCO District Great Bend  
Kind of Job Double Packer

HOLE & TOOL DATA

Total Depth	4930'	Casing Perforations	Top Bottom
Top Packer Depth	4849'	Bottom Packer Depth	4857'
Casing or Hole Size	7 7/8"	Liner or Rathole Size	-----
Formation Tested	Mississippi		
Size Drill Pipe	4 1/2" APIFH	Size Drill Collars	5 3/4" x 63'
Size Bottom Choke	1/2"	Size Surface Choke	3/4"
Size Tool Valve	1"	Size Pilot Valve	-----
Size Hook Wall Packer	-----	Size Rings	-----
Size D. E. Wall Packer	6 3/4"	No. Packers	Two
PRD Device No.	1619	Blanked Off	Yes
Size & Length Anchor	4 1/2" x 42' plus 1 x 4 1/2" x 31' drill pipe		

Price \$215.00  
Second Packer Assembly 75.00  
Safety Joint -----  
Extra Folder Charge -----  
Jars -----  
Total 290.00  
Witnessed By R.E. Roby  
Tester J.H. Guthrie

MUD DATA


Kind Starch  
Weight 9.9 lbs.-gal.  
Viscosity 39.5 Sec.  
Filter Loss 8.2 c. c. Filter Cake 2/32 in.  
BT. P.R.D. No. 294 Blanked Off No

12 Hr. Clock No. 2232  
Est. Gauge Depth Temp. 100 °F  
Pressure Readings Field Office Corrected  
Initial Hydro Mud Pressure 2530 p.s.i.  
Initial Flow Pres. 19 18 p.s.i.  
Tool Open 30 minutes  
Final Flow Pres. 19 18 p.s.i.  
Time Closed In 15 minutes  
Closed in Pres. 209 209 p.s.i.  
Final Hydro Mud Pressure 2506 p.s.i.

REMARKS: Opened tool with a weak blow that decreased until it died in 14 minutes. Recovered 45' of drilling mud.

Amount of Cushion None All depths measured from Kelly Bushing No. Folders Reproduced Five

PRESSURE



Each Horizontal Line Equal to 1000 p.s.i.