

SCOUT TICKET

COUNTY	Clark	STATE	Kansas	DATE	3/28/57
COMPANY	Pure				
FARM	J. C. Harper "E"	NO.	1		
SEC.	13	TWP.	34	RGE.	21
Location in Sec.				ELEV.	1870 DF 1865 61-
Fr. N.	Fr. S.				
Fr. E.	Fr. W.				
C SE NW					
				Harper Ranch	
				5600' Test	

PERFORATIONS	GAS PAYS		CASING RECORD
<i>Sp1</i> Morr 5405	Hollenberg	<i>Schl</i> 4216	112 (200)
" sd 5443-88	Herington	<i>Lans AC</i> 4544	13" 581 (325)
" " 5496-5511	Padock	<i>Warm</i> 5132	8 5/8" 1454 (800)
Miss 5516	Krider	<i>Cher</i> 5288	7"
	Odel	<i>Morr</i> 5406	6"
	Winfield	<i>Miss</i> 5515	5 1/2" 5517/250
	Gage		TD
	U. Ft. Riley		PB
	L. Ft. Riley		Nat
			Acid
			AA
			DEL
			Rock
<i>5405</i> <i>1070</i> <i>13535</i> <i>13110</i>			
Contractor	Unit Drlg. Co.		

4/4/57	Drlg 750	
APR 11 1957	2280	
APR 18 1957	5250	
APR 23 1957	5440-88	Rec 48'
	3' sh.	
	9' sd	grn, fw, tite, glauc, w/lt
		stn, odor, flour, sh lam
	4' sd	grn, fw, tite, glauc, stn
		flour, sh odor
	10 1/2' sd	med gr, stn, pore + perm,
		flour,
	3 1/2' sd	grn, fw, tite, NS
	1 1/2' sd	med gr, qd pore + perm,
		stn, flour
	1' sd	med gr, tite, bldg oil
	7' sd	" " " qd pore, stn,
	1 1/2' sd	fw med gr, tite, NS
	2' sd	" " " fw pore, NS
	5' sd	grn, fw, tite, NS, bldg wtr
	TTD 5480	

DST 5496-68 (SP), op 25 min, mud (W), gas
10 14 min, 8000 MCF, Rec 4050'
mud, FP 1048-830, BHP 2405/

€ 5493-5518

Rec 23'

3 1/2' sh.

1 1/2' sd

2' sd

1' sh

6 1/2' sd

fr, tite, scat str, odor,

fr, shly, " "

sdg

med-cr, scat str, flour, odor

sl. bldg o + g. e 5509-10, fr.

poro + perm

3' sh

1 1/2' sh

1 1/2' siltstone

2 1/2' lm.

sdg, NS.

buff, foss, NS.

DST 5504-18, op 1 hr, Rec 90' mud, FP 0-185,
BHP 270/30

(RTD 5518)

Schl.

WOST

MAY 2 1957

RUEF 400 5515

(12) 5502-05

(12) 5509-12

S/ 120 PM

A/ 1000 mud

S/ 148 BSW

Set Plug e 5480

(24) 5456-62

hole filled w/ SW

MAY 9 1957

RAW 169 e 5481

S/ 85 661s mud

GA. 8820 MCF

16 hr.

SITP 1800 #

50 Perts # CO

(20) 5444-50

SI GAS Well.

HFI

FR 5480

Narr 5444-50