

1-34-14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
50S East Murdock, Wichita, Kansas

Company. SOCONY MOBIL OIL CO.  
Farm. Roxie-Kincaid No. 1  
Estate Unit "A"

SEC. 1 T. 34 R. 14W  
NW SE NE  
1650 FNL, 1800 FWL NE/4

Total Depth. 4865'  
Comm. 11-11-60 Comp. 12-1-60  
Shot or Treated.  
Contractor. Peel Brothers, Inc.  
Issued. 2-25-61

County Barber  
KANSAS



Elevation. 1752' GL

Production. 3,484,000 MCFPD

CASING:

8 5/8" 348' cem w/425 sx.  
4 1/2" 4765' cem w/175 sx.

Figures Indicate Bottom of Formations.

surface soils	40
sand & clay	120
red bed & shells	845
shale	1100
red bed	1200
shale & shells	1870
shale	1995
lime	2470
lime & shale	2558
lime	2660
lime & shale	4178
lime	4865
Total Depth	

TOPS:

Heebner	4008
Toronto	4030
Lansing-Kansas City	4184
Mississippi	4753

Acidized OH 4765-4865' w/1000 gal 6% HCl acid.  
Sand frac OH 4765-4865' w/50,000# 20/40 sand  
and 50,000 gal 6% HCl acid.