

2-34-14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.
Farm- E.K. Sooter No. 1

SEC. 2 T. 34 R. 14W
SW SE NE
990' E, 2310' N NE/4

Total Depth. 4820'
Comm. 3-23-65 Comp. 4-27-65
Shot or Treated.
Contractor. K & E Drlg.
Issued. 9-25-65

County Barber
KANSAS



Elevation. 1686' K.B.

Production. 2,930 MCFGPD, 4 BO

CASING:

8 5/8" 366' w/200 sx cem.
5 1/2" 4818' w/100 sx cem.

Figures Indicate Bottom of Formations.

| | |
|----------------------------|------|
| shale | 105 |
| sand | 135 |
| shale shells | 366 |
| shale | 465 |
| shale, red bed | 1158 |
| shale, shells | 1845 |
| lime, shale | 2180 |
| lime | 2920 |
| lime, shale | 3450 |
| lime | 4720 |
| cherty dolomite, limestone | |
| w/stain, no show | 4760 |
| lime | 4820 |
| Total Depth | |

TOPS:

| | |
|---------------|------|
| Heebner | 3942 |
| Douglas | 3976 |
| Lansing | 4134 |
| B/Kansas City | 4612 |
| Mississippi | 4690 |

DST #1 4712-4785'-Op. 1 hr.,
good blow or air throughout,
Rec. 200' heavy gas and oil
cut watery mud, 2440' muddy
water, 120' salt water, gas
to surface 1 hr., 50 mins.,
too small to measure. TCIP-1851#
45 mins., FCIP-1805# 45 mins.,
FFP-713#, FFP1015#.(Water is
filtrate water)

DST #2 4710-4753'-used straddle
packer, tool op. 2 hrs. gas t
surface in 46 min., too small
to gauge, Rec. 130' slightly GCM,
IFP - 27# 45 mins., FFP 73#,
IBHP 978#, 45 mins, FBHP
1590# 45mins.