

5-34-14W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company. CHAMPLIN OIL & REFINING CO.
Farm. Davis Ranch "G" No. 2

SEC. 5 T. 34 R. 14W
APP C SW SE
105' N & 5' W of C SW SE

Total Depth. 4830'
Comm. 10-21-60 Comp. 11-13-60
Shot or Treated.
Contractor. Armer, Inc.
Issued. 2-4-61

County Barber

KANSAS



Elevation. 1672' DF

Production. 3,120,000 CFG

CASING:

13 3/8" 200.17' cem w/225 sx.
8 5/8" 953.00' cem w/100 sx.
5 1/2" 4825' cem w/50 sx.

Figures Indicate Bottom of Formations.

top soil & red bed	40
red shale & gyp	160
shale & shells	200
red bed, shale & shells	566
shale & shells	1365
shale & shells	1760
shale & lime	3870
sandy shale & lime	3935
lime & shale	4035
lime	4095
lime & shale	4155
lime	4490
cherty lime	4530
lime	4565
lime & shale	4635
lime	4680
lime & shale	4699
lime	4720
cherty lime	4750
Mississippi lime	4780
lime	4790
lime & shale	4820
Mississippi lime	4830
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Heebner	3933	3931
Toronto	3947	3946
Douglas	3971	3968
Lansing	4124	4136
Base Kansas City	4611	4611
Marmaton	4619	4618
Cherokee	4692	4696
Mississippi	4701	4705