


7-34-14W

Company- BACHUS OIL COMPANY  
 Farm- Davis Ranch "C" No. 1

SEC. 7 T. 34 R. 14W  
 C SW SE

Total Depth. 4840'  
 Comm. 6-19-62 Comp. 7-4-62  
 Shot or Treated.  
 Contractor.  
 Issued. 2-16-63

County Barber  
 KANSAS



CASING:  
 13 3/8" 238' cem w/275 sx.

Elevation. 1662' KB

Production. DRY

Figures Indicate Bottom of Formations.

alluvium	40
shale & shells	240
red bed & shells	965
shells & shale	1139
shale	1635
lime & shale	1770
lime	1945
lime & shale	2050
lime	2140
shale & lime	2220
lime	2290
lime & shale	2440
lime	2480
lime & shale	3475
lime & chalk	3555
chalk	3715
lime & shale	3725
shale	3918
shale & sand	4051
shale, sand & lime	4175
lime	4210
chalk & lime	4295
chalk lime & shale	4350
lime	4480
lime & shale	4510
lime	4555
lime & shale	4658
lime	4772
Mississippi chert & dolomite	4840 RTD
Total Depth	

TOPS:

Heebner	3960
Douglas	3996
Lansing	4170
Marmaton	4672
Cherokee	4760
Mississippian	4770

DST #1 4773-4792' Op 1½ hrs. Rec. 30'  
 VSO & GCM. FP 20-20, BHP 130/30-130/30.  
 HH 2560 - 2560. T. 112 degrees.

DST #2 4792-4840' Op 1 hr. Rec. 60'  
 VSO & GCM. FP 40-50, BHP 140/30-90/30.  
 HH 2620-2620. T. 113 degrees.