


10 - 34 - 14W

Company - PHILLIPS PETRO.CO.  
 Farm - Wheatley No. 1.

SEC. 10 T. 34 R. 14 W  
 NWc NW

Total Depth. 5307' PB 4756'  
 Comm. 7-24-44 Comp. 10-4-44  
 Shot or Treated.  
 Contractor.  
 Issued. 12-23-44

County. Barber  
 KANSAS



CASING:  
 10" 1142'  
 7" 4658'

Elevation. \_\_\_\_\_

Production. Dry

Figures Indicate Bottom of Formations.

red bed & shells	270
shale & shells	795
shale & shells	1145
anhydrite	1165
shale sdy & shells	1460
salt & shale	1515
shale & shells	1750
lime brkn	2122
shale brkn	2223
lime & shale	2324
lime brkn	2482
lime & shale	2494
lime	2558
lime & shale	2962
shale brkn	3072
lime & shale	3218
lime	3380
lime & shale	3524
lime	3584
lime & shale	3898
lime	4015
lime & shale	4063
lime	4535
lime & shale	4575
lime	4727
lime	4770
shale	4798
lime	4830
shale cherty	4843
lime & shale	4865
shale green	4900
shale & lime	4935
lime	4968
shale	4988
lime	5003
shale	5026
lime	5097
cherty lime	5106
lime	5165
shale & sand	5234
shale	5264
sand, shale & lime	5294
lime Arbuckle	5307
Total Depth	

Drlg out 100 qts. N G 4677-4711  
 2000 gals Acid  
 tested 83,000 cu ft gas  
 18 gals WPH  
 D & A

Tops:  
 Lansing KC 4081  
 Miss 4656  
 Kinderhook 4849  
 Chatt 4945  
 Cherty Viola 5016  
 Xlyn Viola 5125  
 Simpson 5156  
 Arbuckle 5275

Plugged back to 4756