

17-34-14W

KANSAS
**WELL COMPLETION REPORT AND
 DRILLER'S LOG**
State Geological Survey
WICHITA BRANCH

S. 17 T. 34S R. 14 ^W
 Loc. NW $\frac{1}{4}$ SW $\frac{1}{4}$ SW $\frac{1}{4}$
 County Barber

API No. 15 — 007 — 21,198
 County Number

Operator
Texas West Oil & Gas Corporation

Address
1480 Midland National Bank Tower Midland, TX 79701

Well No. 1-A Lease Name Z-Bar Ranch "17"

Footage Location
1025 feet from (E) (S) line 355 feet from (E) (W) line

Principal Contractor Dunne-Gardner Petroleum Geologist Ed Sander.

Spud Date 04/14/81 Date Completed 06/01/81 Total Depth 4875' P.B.T.D. 4846'

Directional Deviation _____ Oil and/or Gas Purchaser Cities Service Gas Company

640 Acres
 N

Locate well correctly
1610'

Elev.: Gr. _____

DF 1621' KB 1623' Datum

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{2}$ "	8-5/8"	23#	883'	Class "A"	435	3% CaCl ₂
Production	7-7/8"	4 $\frac{1}{2}$ "	10.5#	4874'	50-50 Poz Poz "A"	200 200	2% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1 shot/2'	0.41"	4784-4816'

Size	Setting depth	Packer set at
2-3/8"	4665'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/500 gals 7 $\frac{1}{2}$ % Mud Acid; F/26,000 gals 2% KCL wtr; 506,000 SCF	4784-4816'
Nitrogen; 10,000# 20-40 Sand & 5000# 10-20 Sand	

RECEIVED
 STATE CORPORATION COMMISSION

INITIAL PRODUCTION

JUN 22 1981

Date of first production 06/01/81 Producing method (flawing, pumping, gas lift, etc.) Flowing

RATE OF PRODUCTION PER 24 HOURS
 Oil Zero bbls. Gas CAOF: 8546 MCF Water None bbls. CONSERVATION DIVISION
 Wichita, Kansas

Disposition of gas (vented, used on lease or sold) Vent during 4-Point Test (SIWOPL Conn.) Producing interval (s) 4784-4816'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note 2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Texas West Oil & Gas Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Gas

Well No.

1-A

Lease Name

Z-Bar Ranch "17"

S 17 T 34S R 14 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale	0	194	Douglas sh	4038 -2415
			Brown ls	4146 -2523
Sand & Shale	194	886	Lansing-KC ls	4154 -2531
			Stark sh	4570 -2927
Shale	886	2367	Marmaton grp	4666 -3043
			Cherokee grp	4748 -3043
Shale & Lime	2367	3390	Miss. ls	4782 -3159
Lime	3390	3924		
Lime & Shale	3924	4173		
Lime	4173	4875		
Rotary Tool Depth	4875			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Alice Sandell

Signature

Office Manager

Title

9 June 1981

Date

3-20-1981

