

Total Depth. 5401' P.B. 4930'
Comm. 4-30-36 Comp. 8-3-36
Shot or Treated.

Contractor. Southern & Thurmond

Issued. 9-12-36 Rotary O-4718
Cable 4718-5401

SEP 12 1936



CASING:
12 1/2" 296'
7" 4718'

Elevation.

Production. 7,000,000 Gas.

Figures Indicate Bottom of Formations.

cellar	6	Cored 4585-4600	Shot 60 Qts 5205-26
red rock & lime	100	Oil saturation showing	Show free oil
shale & shells	185	lime 4610	1/5 B of Oil
red rock	235	lime, some shale 4620	Slight inc in gas
sand	285	Corod 4610-24	Show of Viola 5204-26
shale	315	Bottom 5' showed oil stain	With 270 Qts. no inc
shale & lime shells	1150	4610-20	in oil
spl't	1300	brkn lime 4624	After second shot, oil
shale & lime shells	1880	lime & shale breaks 4665	show 5208-22
brkn lime	2030	lime & shale & shells 4680	lime 5294
lime	2150	shale 4695	SLM 5277-89
shale & lime shells	2175	lime 4718	lime brkn hrd 5300
lime	2225	slight sh gas 4730-35	lime 5355
shale & lime shells	2240	lime 4754	lime grey 5363
lime	2345	shale green & lime 4764	shale green 5395
shale & lime shells	2405	lime 4780	lime & sand with
lime	2415	shale black 4796	crystals 5401
shale & lime shells	2595	lime brown 4804	Total Depth
lime	2665	lime & chert 4835	Plugged Back 4930
brkn lime	2770	Increase gas 4813-15	Completed as gas well.
shale & lime shells	2915	Est. 250,000	Shot 60 Qts. 4813-32
lime	2960	Run measuring lime	60 Qts. 5205-26
sdv shale	2975	4817-20 Top of Gas	270 Qts. 5204-26
lime	3005	Corrected SLM 4816	
shale & lime shells	3080	Increase Gas 4820-22	
lime	3090	Est. 500,000 cu ft gas.	
shale & lime shells	3105	More gas 4825-29 slight	
lime	3130	shows.	
shale & lime shells	3300	Trace of oil	
lime	3340	Est. 1,500,000 gas	
shale	3365	lime 4893	Top K.C. 4215
lime	3410	Shot 4813-32 with 60 Qts.	Top Chat & lime 4796
shale & lime shells	3430	Increase gas 1,500,000	Top Chattanooga 5145
lime	3570	to 5,000,000.	Top Viola 5204
brkn lime	3615	lime hrd 4900	Top Simpson 5395-5401
shale & lime shells	3655	lime 5015	HFW 5401
lime	3695	lime blk 5030	Gas 4813-28
shale & lime shells	3900	lime grey 5040	Core Sh Oil 4610-20
lime	3930	lime 5060	Est gas 500,000 4825-28
shale & lime shells	3970	shale & dolomite lime 5090	Gas 4813-22
lime	3995	shale green & some brown	Inc. Gas 4822-29
shale & lime shells	4010	shale 5098	Est. 1,500,000 Gas
lime	4030	lime 5109	After shot gaged open
shale & lime shells	4215	lime hrd 5119	flow 4,475,000 cu ft
Cored 4215-30, 6' rec.	4215	lime brkn 5140	Show of oil in samples
lime hrd	4250	lime 5145	5208-22
lime (Cored)	4265	shale blk 5204	After shot showed free
shale & lime shells	4275	lime 5208	oil.
lime	4310	SLM 5198-5205	
shale & lime shells	4420	Top of Viola 5204-08	
lime	4525	No showing of oil	
shale & lime shells	4530	1st sh oil 5210-12	
oh tty lime hrd	4560	Drilled screw 5208-12	
lime	4570	Washed oil in	
shale & lime shells	4585	samples 5208-22	
lime hrd	4605	lime hrd dense 5222	
shale		lime 5226	