

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

19-34-14W

Company- TIME PETROLEUM

Farm- Davis Ranch

No. 2

SEC. 19 T. 34 R. 14W,
C NE SW

Total Depth. 4920'

Comm. 4-15-64

Comp. 4-27-64


Shot or Treated.

Contractor. Strata Drlg.

Issued. 7-18-64

County Barber

KANSAS



CASING:

8 5/8" 278' cem w/ 200 sx

Elevation. 1697' KB

Production. DRY

Figures Indicate Bottom of Formations.

red bed	497
shale & red bed	1005
shale	1660
shale & shells	2025
lime	2350
lime & shale	2650
shale & shells	2870
lime & shale	3275
lime	3450
lime & shale	3828
shale	4005
shale & lime	4228
lime	4255
lime & shale	4360
lime	4740
lime & shale	4809
lime	4834
lime & chert	4870
lime	4920
Total Depth	

TOPS: SMP

Heebner	4023
Douglas	4088
Lansing	4227
Cherokee sand	4841
Mississippi	4851

DST# 1 4837-4870' Tool op 1 hr. weak blow for 5 min. Flushed tool. Rec. 20' mud, no show of oil or gas. ISIP 73#. IFP 42#. FFP 52#. FSIP 52# in 1 hr.

DST # 2 4866'4900' packer failed

DST #2 Return 4830'4900' weak blow 2 hrs. Rec. 20' mud no show oil or gas. ISIP 179#. IFP 10#, FFP 16#. FSIP 63# in 1 hr.

DST # 3 4900'-4920' tool op 2 hrs. weak to fair blow. Rec. 30' mud. ISIP 147# IFP 42#. FFP 50#. FSIP 115# in 1 hr.