

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


22-34-14W

Company- SOCONY MOBIL OIL CO.
Farm- Mary Brattin No. 1

SEC. 22 T. 34 R. 14W
NE NW SW

Total Depth. 4970'
Comm. 6-1-60 Comp. 11-2-60
Shot or Treated.
Contractor. Peel-Brothers
Issued. 1-14-61

County Barber
KANSAS



Elevation. 1675' DF

CASING:
5/8" 1179' cem w/225 sx.
4 1/2" 4929' cem w/80 sx.

Production. Dry

Figures Indicate Bottom of Formations.

sand	10
red bed	200
red bed & shale	770
shale	1260
shale & shells	1870
lime	2550
lime & shale	3495
lime	3550
lime & shale	3655
lime	3770
shale & lime	3915
lime	4008
lime & shale	4215
lime	4815
lime	4970
Total Depth	

TOPS: SCOUT

Elgin	3873
Heebner	4026
Toronto	4034
Lansing	4199
Mississippi	4823

Perforations:

4828-4850' w/52 shots by McCullough
4870-4890' w/40 shots by McCullough

Temp. Abd.