


25-34-14W

Company- E. H. ADAIR OIL COMPANY
 Farm- Blunk "C" No. 1

SEC. 25 T. 34 R. 14W
 C W/2 NE/4

Total Depth. 4745'
 Comm. 9-30-59 Comp. 10-12-59
 Shot or Treated.
 Contractor. Graham-Michaelis Drilling Co.
 Issued. 1-2-60

County Barber
 KANSAS



Elevation. 1570 KB

Production. Dry

CASING:

8 5/8" 347' cem w/200 sx.

Figures indicate Bottom of Formations.

clay	10
sand	25
redbeds & shale	1798
shale & lime	2793
shale	3112
shale & lime	3748
sand	3817
shale	3880
shaley lime	3916
black shale	3919
lime	3922
shale	3931
shaley lime	3996
shale	4091
lime	4099
porous lime	4107
lime	4131
porous lime	4140
lime	4154
porous lime	4179
lime	4520
black shale	4524
lime	4550
black shale	4555
lime	4581
black shale	4585
lime	4608
limey shale	4619
lime	4635
shale	4638
lime	4656
shale	4659
cherty lime	4669
shaley lime	4676
shale	4680
lime	4687
cherty dolomite	4745
Total Depth	

Dst No. 1 Open 1 1/2 hrs. Gas to surface in 54 min. Now enough to gauge. Rec. 105' gas-cut mud. ISIP-1360# in 20 min. FSIP-1170# in 20 min. IFP-0. FFP-0.

DST #2 4720-45 Weak blow for 1 hour. Recovered 20' of mud. ISIP-370# in 20 minutes. FSIP-0 in 20 minutes. No flow pressures.

TOPS:

Elgin sand	3748
Heebner shale	3916
Lansing Kansas City	4091
Base Kansas City	4581
Mississippi dolomite	4687