

WELL LOG BUREAU-KANSAS GEOLOGICAL SOCIETY

503 East Murdock,


Wichita, Kansas

Company. WILLIAM GRUENERWALD
Farm. Farley No. 2SEC. 29 T. 34 R. 14W
C NW NW

29-34-14W

Total Depth. 4771'
Comm. 2-25-58 Comp. 3-7-58Shot or Treated.
Contractor. Patton Drilling Co.
Issued. 8-6-60

County Barber



Elevation. 1550' RB

8" @ 750'
5 1/2" @ 4771' w/250 sks. cem.

Production. 3,800,000 CFG

Figures Indicate Bottom of Formations.

SCOUT TOPS:

| | |
|-------------|------|
| Heebner | 3890 |
| Toronto | 3900 |
| Douglas | 3930 |
| Lansing | 4090 |
| Mississippi | 4733 |

2-4-58 Perforated:

4748' - 4738', 71 - 15/32

Bullets.

Faint show of gas.

2-4-58 Acidized:

With 500 gals. Dowell Mud
Acid.Well kicked off and cleaned
out.

Estimated volume 200 MCF,

2-5-58 Frac. Treatmcht:

10,000 gals. Acid Petrofrac.
10,000 lbs. sand.Shut in 4 1/2 hours; well un-
loaded without swabbing,
blown for 5 hours & shut in.

Estimated volume 2,500 MCF

2-7-58 Ran tubing under pressure
(Otis Engr. Co.)2-8-58 Well shut in for Cities
Service Gas Co. open flow
test & pipe line connection.2-12-58 Shut in pressure -
1620 psi