

30-34-14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

SCHERMERHORN OIL CORP. &  
Company- KENWOOD OIL COMPANY  
Farm- Davis Ranch "C" No. 1

SEC. 30 T. 34 R. 14W  
C NE SW

Total Depth. 4930'  
Comm. 9-21-59 Comp. 10-8-59  
Shot or Treated.  
Contractor. Strata Drilling, Inc.  
Issued. 5-21-60

County Barber  
KANSAS



Elevation. 1682 GR

8 5/8" 259.33 cem. w/175 sx.  
4 1/2" 4929.5' cem. w/60 sx.

Production. 3,000,000 CFG

Figures indicate Bottom of Formations.

surface clay & sand	50
red bed & shells	825
shale	1710
shale, lime strks.	2030
lime & shale	3620
shale	3750
shale & lime strks.	3850
lime, shale & sand	3975
shale & lime	4192
lime	4405
lime & shale	4502
lime	4724
lime & shale	4780
lime	4855
lime & chert	4905
lime	4930
Total Depth	

TOPS: SCOUT	
Heebner	4058
Toronto	4072
Lansing	4250
Base Kansas City	4768
Marmaton	4780
Mississippi	4891

DST #1 4872-4905'

DST #2 4906-4930'