

35-34-14W ✓

**KANSAS DRILLERS LOG**

State Geological Survey  
WICHITA, BRANCH

S. 35 T. 34S R. 14 W

API No. 15 — 007 — 20362  
County Number

Loc. SW NE SW

County Barber

Operator  
Cities Service Oil Company

Address  
700 Sutton Place Bldg., 209 E. William, Wichita, Kansas 67202


Well No. 1 Lease Name Baier "B"

Footage Location  
1660 feet from (N) (S) line 1710 feet from (E) (W) line

Principal Contractor D. R. Lauck Oil Company, Inc. Geologist Bill Jacques

Spud Date 11-7-75 Total Depth 4880 P.B.T.D.

Date Completed 1-13-76 Oil Purchaser None



Elev.: Gr. 1576

DF 1579' KB 1581'

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24.7#	401'	Pozmix	300	2% CaCl <sub>2</sub>
Production	7-7/8"	4-1/2"	10.5#	4879'	Howco	350	10% Salt
					Class A	250	10% Salt .75% CFR-2

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	1/2"	4810-25

**TUBING RECORD**

Size	Setting depth	Packer set at
2-3/8"	4839.44'	

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
Frac. w/5000 Gal. Frac RF50J267 followed by 50,000 gal. containing 25,000# 20-40 sand then 25,000# 10-20 sand spotted	4810'-25'
500 gal. 7-1/2% BDA	4810'-25'

**INITIAL PRODUCTION**

Date of first production Waiting on Gas Contract	Producing method (flowing, pumping, gas lift, etc.) Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB
	497
Disposition of gas (vented, used on lease or sold)	Producing interval (s) 4810'-25'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **Cities Service Oil Co.** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: **Gas**

Well No. **1** Lease Name **Baier "B" #1**

S **35** T **34SR 14** 


**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
See attached.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p style="text-align: right;">             Signature  <b>W. J. Devaney</b>            Region Operations Manager            Title  <b>January 16, 1976</b>            Date         </p>
---------------	--

32-34-14

35-34-14W

Cities Service Oil Company - Baier "B" #1  
SW NE SW Sec. 35-34S-14W  
Barber County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.  
301 S. Broadway  
Wichita, Kansas 67202

Commenced: November 6, 1975  
Completed: November 19, 1975

Drillers Log

Shale	375
Red Bed	445
Sand & Shale	730
Gyp	768
Shale	1160
Shale & Lime Shells	1835
Shale & Lime	3900
Lime & Shale	4200
Lime	4880 RTD