

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


11-34-14W ✓

Company- SOCONY MOBIL OIL CO.
 Farm- Roxie Kincaid Est. No. 1

SEC. 11 T. 34 R. 14W
 50' W of NE SE SW

Total Depth. 4870'
 Comm. 7-15-60 Comp. 11-3-60
 Shot or Treated.
 Contractor. Peel Brothers, Inc.
 Issued. 1-28-61

County Barber
 KANSAS



CASING:
 8 5/8" 353' cem w/425 sx.
 4 1/2" 4785' cem w/175 sx.

Elevation. 1618' GL

Production. 1,090,000 MCFPD

Figures Indicate Bottom of Formations.

redbed	30
water & redbed	255
redbed, shale & shells	845
shale & shells	1370
shale & lime	1890
broken lime	1960
lime	2110
lime & shale	4103
lime	4870
Total Depth	

TOPS:	
Heebner	3921
Toronto	3936
Douglas	3959
Lansing-Kansas City	4101
Marmaton	4616
St. Louis	4717

Acidized OH 4785' to 4870' w/1000 gal.

BDA acid.

Sand frac OH 4785' to 4870' w/45,000# 10/20 sand
 in 45,000 gal 5% HCl acid.

Perf. 4726-65' w/78 holes. Acidized w/1000 gal
 BDA.

Sand frac perf 4726-65' w/20,000# 20/40 sand +
 5,000# 10/20 sand + 25,000 gal. 6.2% acid.

Treat perf 4726-65' and OH 4765'-4870' w/2000
 gal. 6% HCl w/6000# CaCl.