

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


11-34-14W

COMPANY **SHENANDOAH OIL CORPORATION**
 FARM **MILDRED SIMS "A"** NO. **1**

SEC. **11** T. **34** R. **14W**
 LOC. **C NE NW**

TOTAL DEPTH **4840'**
 COMM. **5-12-67** COMP. **6-27-67**
 SHOT OR TREATED
 CONTRACTOR **Leben Drlg.**
 ISSUED **8-26-67**

COUNTY **Barber**



CASING

20	10
15	8 5/8" 394.15' cem w/ 250 sx
12	6
13	5
	4 1/2" 4838' cem w/ 200 sx

ELEVATION **1642'**

PRODUCTION **4 PT OF 1900 MCF/GPD**
Plus 11B0 Plus 13 BWPD - SIT# 122
 #/ Miss 4752-59

0	1684	Redbed
1684	1830	Shale, Shells
1830	2020	Lime, Shale
2020	2716	Lime
2716	4251	Lime, Shale
4251	4840	Lime
	4840	<u>RTD - Set 4 1/2" Casing</u>

8 5/8" new 70% surface casing set 394.15' cemented with 250 sacks Common, 2 1/2 cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Mildred Sims A-71 Well, located C NE NW of Section 11, Township 34 South, Range 14 West, Barber County, Kansas, as reflected by the records of Leben Drilling, Inc.

- TOPS: LOG
- Heebner 3923
 - Toronto 3937
 - Douglas 3964
 - Lansing Kansas City 4116
 - Base Kansas City 4534
 - Mississippi Cht 4708

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 29th day of May, 1967.

Glenn Perkins