

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

17-34-15W

Company- BARBARA OIL
Farm- Brach

No. 1

SEC. 17 T. 34 R. 15W
NE NE SW

Total Depth. 5549'


Comm. 2-13-54

Comp. 3-23-54

Shot or Treated.

Contractor. R. C. Patton

Issued. 7-17-54

County Barber
KANSAS

CASING:

15 1/2" 56' cem w/100 sx

10 3/4" 789' cem w/500 sx

Elevation. 1595'

Production. Dry

Figures indicate Bottom of Formations.

sand	23
red clay	35
red rock	75
sand	95
red bed & shale	775
shale & shells	1100
salt, shale & shells	1220
shale gry & shells	1248
shale & shells	1880
lime & shale	1925
anhydrite & shale	2005
lime	2105
lime & shale	2280
shale	2365
lime & shale	3970
shale sdy	4015
lime & shale	4132
lime brkn	4162
lime & shale, chert	4220
lime & shale	4243
lime brkn	4300
lime & shale	4414
lime	4433
lime & shale	4551
lime	4574
shale	4596
lime	4609
lime & shale	4725
lime	4760
lime & shale	4840
lime	4866
shale	4891
lime & shale	4992
shale	5077
lime & shale	5115
lime	5155
lime cherty	5168
lime	5315
lime & shale	5386
sand	5402
lime & shale	5420
lime	5458
lime, chert	5491
lime	5549

Total Depth

Tops: Scout	
Douglas	3968
Lansing	4126
Viola	5103
Simpson Shale	5252
Simpson Sand	5295
Arbuckle	5412

Schlumberger Tops:	
Douglas Sand	3970
Lansing	4127
Mississippi	4770
Viola	5122
Arbuckle	5412