

36-34-15W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CHAMPLIN OIL & REF.
Farm- Davis Ranch"Q" No. 1

SEC. 36 T. 34 R. 15W
Approx. C W/2

Total Depth. 4873
Comm. 9-21-64 Comp. 10-10-64
Shot or Treated.
Contractor. H-30, INC.
Issued. 1-2-65

County Barber
KANSAS



CASING: 13 3/8" 199.35' 225 sx.cem.
8 5/8" 349.79' 100 sx.cem.
5 1/2" 4873' 100 sx.cem.

Elevation. 1536' DF.

Production. 19,500 MCF/DPD

Figures Indicate Bottom of Formations.

sand	70
shale & redbed	550
rat hole	898
reaming to 12 1/4"	200-850
shale & shells	1150
shale & shells	1805
shale & lime	1995
lime & shale	2280
lime	3305
lime & shale	3450
lime	3565
lime & shale	3750
lime & sdy. shale	3850
shale & lime	4015
lime & shale	4120
lime	4180
lime & shale	4210
lime w/some shale	4265
lime	4310
lime & shale	4375
lime	4601
lime & shale	4635
lime	4666
lime w/some shale	4713
lime	4745
lime & shale	4770
lime & sdy. shale	4798
cherty lime	4840
lime (cherty)	4870
Total Depth	

ELECTRIC LOG TOPS:

Heebner	3941
Lansing Kansas City	4137
Marmation	4667
Cherokee	4770
Mississippian	4802
Cowley	4850
Log T.D.	4874