

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

18-34-15W

Company- HONAKER-DAVIS DRILLING COMPANY, et al
Farm- Wells No. 1

SEC. 18 T. 34 R.15W
NE NE SW

Total Depth. 5353'

Comm. 4-8-57

Comp. 5-1-57


Shot or Treated.

Contractor. Honaker-Davis Drilling Company

Issued. 3-1-58

County Barber

KANSAS



CASING:
8 5/8" 261' cem w/250 sx
5 1/2" 4850' cem w/175 sx

Elevation. 1582' RB

Production. 37 BOPD

Figures Indicate Bottom of Formations.

sand	90
shale	105
sand	120
red bed & shale	220
shale & shells	325
red bed	510
shale & shells	1300
shale, salt & shells	1690
shale & shells	1940
shale & lime	2180
shale	2280
shale & shells	2360
shale & lime	2890
shale & shells	3040
shale	3210
shale & lime	3330
shale, lime & shells	3446
shale & shells	3555
shale & lime	4230
lime	4557
shale & lime	4710
lime	5331
lime & chert	5334
lime	5353-RTD
Total Depth	

DRILL STEM TEST #3

4541-4557

Johnston Testers

Blow: Good to Fair

Recovery: 660' gas

80' SO & GCM

Pressures: IBHP 1120#

FBHP 185#

FP 0-0#

DRILL STEM TEST #4

4775-4805*

Johnston Testers

Blow: 768,000 cu. ft. gas

Recovery: 65' SO & GCM

Pressures: IBHP 1895#

FBHP 1865#

IFP 170#

FFP 190#

* NOTE: This test covered the lower part of the Cherokee sand and the upper part of the Mississippian.

DRILL STEM TEST #5

4790-4825

Johnston Testers

Blow: Fair

Recovery: 40' SGCM

Pressures: IBHP 1430#

FBHP 130#

FP 0-0#

TOPS:

Heebner	3918
Douglas Shale	3954
Lansing-Kansas City	4124
Mississippian	4784
Kinderhook Lime	5072
Chattanooga	5106
Viola	5132
Simpson Shale	5329
Simpson Sand	5334

DRILL STEM TEST #1

4164-4191

Johnston Testers

Tool open: 20" - 60" - 20"

Blow: Good

Recovery: 900' water

Pressures: IBHP 1710#

FBHP 1690#

IFP 130#

FFP 570#

DRILL STEM TEST #2

4491-4501

Johnston Testers

Blow: Good

Recovery: 840' gas, 140" SGCM

Pressures: IBHP 1855#

FBHP 1655#

IFP 25#