

15-033-20111

and

BUTTONWOOD PETROLEUM, INC.

4-34-16W

OCTOBER 19, 1988

MERRILL # 1
SEC. 4 T34S R16W
COMANCHE COUNTY, KANSAS

TD: 5050'.
8-5/8" 24# K-55 @ 550'.
4-1/2" 9.5# K-55 @ 5049'.
2-3/8" 4.7# J-55 @ 4606'.
PERFORATIONS: 4892'-4921'.

PLUGGING PROCEDURE

- 1.) MIRU WELL SERVICE RIG, N/D TREE AND N/U 7-1/16" X 3M DBL RAM MANUAL BOP. TOH LAYING DOWN TUBING. LEAVE 1200'(+/-) STANDING BACK IN DERRICK.
- 2.) R/U WEDGE WIRELINE CO. AND SET CIBP @ 4800'. DUMP 2 SX CLASS H CEMENT ON TOP OF PLUG. FREE POINT AND JET CUT 4-1/2" CASING. R/D WIRELINE. LOAD HOLE W/9.0#/GAL MUD, AND TOH LAYING DOWN CASING.
- 3.) TIH OPEN ENDED W/ TUBING AND SPOT 50 SACK PLUG ACROSS ANHYDRITE. PULL UP AND SPOT 50 SACK PLUG IN AND OUT OF 8-5/8" CASING. LAY DOWN TUBING.
- 4.) CUT OFF 8-5/8" CASING 3' BELOW GROUND LEVEL, DUMP 10 SX CEMENT IN SURFACE AND WELD ON STEEL PLATE. R/D WELL SERVICE RIG, RESTORE LOCATION.

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1988

CONSERVATION DIVISION
Wichita, Kansas

NOV 01 1988
KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH