

5-34-17W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- PURE OIL CO.  
Farm- Hazel Beals No. 1

SEC. 5 T. 34 R. 17W  
C NE NW

Total Depth. 5940'  
Comm. 10-26-55 Comp. 12-30-55  
Shot or Treated.  
Contractor.  
Issued. 3-31-56

County Comanche  
KANSAS



CASING:  
13" 246'  
5" 5799'

Elevation. 1860'

Production. 3,500,000 CFG/D

Figures indicate Bottom of Formations.

NO LOG AVAILABLE

Tops: Cont.  
Simpson Dolomite 5700  
Simpson Sand 5741  
Arbuckle 5832

- 2600-2710 gray mic., shale
- 2730 gray-buff suc. dolo.
- 2950 gray silty shale w/wh-gray, lime stringers.
- 3005 wh. dense-f. xln lime.
- 3210 gray-brown shale w/buff lime strings.
- 3235 gray-buff f. xln lime.
- 3350 gray silty shale.
- 3475 buff-gray m. xln-dse lm col at top.
- 3495 gray shale
- 3605 buff-gray f. sln-dense lm.
- 3900 gray limy shale w/wh-gray lime stringers.
- 3945 wh-gray, f. xln-dense lm.
- 4025 gray sdy shale
- 4080 wh-gray f. gr ang sst.
- 4120 gray shale
- 4150 gray-black sh w/brn lm stringers.
- 4208 wh-buff f. xln-dense lime
- 4260 gray f. gr mic sst.
- 4340 gray sdy mic. shale
- 4425 buff-gray f. xln-dse lm.
- 4430 dark-gray lmy shale.
- 4540 wh-buff f. xln-dse lime.
- 4570 gray shale
- 4675 wh-gray f. xln-dse lime.
- 4695 dark gray shale
- 4730 buff f. xln-dse ooc. lime.
- 4780 gray-blk shale.
- 4830 buff-dk gray silty lime.
- 4850 gray-green lmy shale
- 4870 buff dse lime.
- 4900 gray-brown-black lmy shale.
- 4980 wh-buff-brown f. xln chty lime.
- 5030 gray-green-black shale w/lm stringers.
- 5048 gray-black shale w/chty cong at base.
- 5110 wh med-coarse xln lime.
- 5130 buff suc. dolomite
- 5170 wh-buff med-coarse xln cherty dolomite lime.
- 5260 wh-buff m. xln-suc cherty dolo.
- 5550 gray f. xln-f. suc. shly chty dolo.
- 5590 gray green shale
- 5660 gray-buff f. xln-suc. chty dolomite lime.
- 5700 tan-buff m. xln dolo lime.
- 5740 gray-brown f.-m. xln chty dolo.
- 5790 wh-gray-med. coarse gr sd.
- 5832 gray-green splintery sh.
- 5940 gray-buff-tan f.-coarse xln. rhombic dolo.

Perf. 92 shots 4393-4416  
(Lansing)

Total Depth

- Tops:
- LeCompton Lime 3920
- Elgin 3999
- Heebner 4121
- Douglas 4208
- Lansing 4341
- Marmaton 4903
- Mississippian 5048
- Viola 5594