

OCT 24 1970

dup
DRILLERS LOG

GUSS NO. 1

15-033-20065

16-34-17W
n/2 S/2 SE

app

Dry/arb.

CASING RECORD:	OPERATOR:	Yucca Petroleum Co.	DESCRIPTION:
8-5/8" @ 397'	CONTRACTOR:	Sage Drilling Co., Inc.	1110'FSL & 1070'FEL
w/250 sax cement	COMMENCED:	May 21, 1970	Sec. 16-34S-17W
TOTAL DEPTH:	COMPLETED:	June 7, 1970	Comanche Co., Kansas
6125'			ELEVATION: 1764 KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed & Sand	0	215	
Red Bed, Shale & Shells	215	630	
Shells & Shale	630	1059	
Red Bed & Shale	1059	1695	
Shale & Shells	1695	2095	
Shale, Shells & Lime	2095	2192	
Lime & Shale	2192	2905	
Shale & Lime	2905	3705	
Sandy Shale	3705	3985	
Lime & Shale	3985	4115	
Lime	4115	4330	
Shale & Lime	4330	4400	
Lime	4400	4990	
Lime & Chert	4990	5010	
Lime, Shale & Sand	5010	5084	
Lime	5084	5181	
Mississippi	5181	5625	
Lime	5625	5803	
Lime & Chert	5803	5910	
Lime, Chert & Sandy Lime	5910	5970	
Sandy Lime & Chert	5970	6008	
Lime & Chert	6008	6066	
Cherty Lime, Shale & Arbuckle	6066	6125	

~~RECEIVED~~
~~STATE CORPORATION COMMISSION~~
~~JUL 1 1970~~
~~CONSERVATION DIVISION~~
~~Wichita, Kansas~~

Jops
LKC 4398
Mississippi 5110
Viola 5748
Arbuckle 6082

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By

T. M. McCaul, Jr.

T. M. McCaul, Jr.

