

SIDE ONE

State Geological Survey

WICHITA, KANSAS
AFFIDAVIT OF COMPLETION FORM5-34-2W
(REV) ACO-1
RD

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).
KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR McGinness Oil CompanyAPI NO. 15-191-21,413ADDRESS 1026 Union Center BuildingCOUNTY SumnerWichita, Kansas 67202FIELD AB'd Jindra**CONTACT PERSON Douglas H. McGinnessPROD. FORMATION N/APHONE 316-267-6065LEASE JindraPURCHASER N/AWELL NO. #1

ADDRESS _____

WELL LOCATION S/2 SW NWDRILLING Big Kat, Inc.300 Ft. from South Line and


CONTRACTOR

600 Ft. from West Line ofADDRESS 250 N. Rock Road, Suite 240the NW SEC. 5 TWP. 34S RGE. 2WWichita, Kansas 67218

WELL PLAT

PLUGGING Allied Cementing Company, Inc.

CONTRACTOR

ADDRESS P. O. Box 31Russell, Kansas 67665

KCC
KGS ☒
(Office
Use)

TOTAL DEPTH 4499' PBTD N/ASPUD DATE 4-08-82 DATE COMPLETED 4-20-82LEVEL: GR 1139' DF _____ KB 1144'DRILLED WITH ~~X CABLE~~ (ROTARY) ~~X AIX~~ TOOLSAmount of surface pipe set and cemented 257' w/200 sx. DV Tool Used? _____

A F F I D A V I T

STATE OF Kansas, COUNTY OF Sedgwick SS, I, _____Douglas H. McGinness OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,DEPOSES THAT HE IS President ~~X (FOR)~~ (OF) McGinness Oil CompanyOPERATOR OF THE Jindra LEASE, AND IS DULY AUTHORIZED TO MAKETHIS AFFIDAVIT AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ONSAID LEASE HAS BEEN COMPLETED AS OF THE 20 DAY OF April, 1982, AND THAT

INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

RECEIVED
STATE CORPORATION COMMISSION
5-5-82
CONSERVATION

W-C-4E-2

SIDE TWO

5-34-2w

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Top Soil	0	40		
Shale	40	830		
Shale & Sand	830	1020		
Shale	1020	1860		
Lime & Shale	1860	4499		
 <u>Sample Tops:</u>				
Kansas City	3420	(-2276)		
B/Kansas City	3699	(-2555)		
Mississippi	4094	(-2950)		
Kinderhook	4433	(-3289)		
Viola	4484	(-3340)		
Simpson Dol.	4497	(-3353)		
 <u>DST #1</u>				
from 4492-4499				
30-30-45-45				
1594-188-596-673-1024-1584				
Gas in 50 min. - 8,090 cub ft.				
Recovered 20' GCM, 900' GMO,				
1300' GOCMW.				
T-146°F				
Loss Circulation				

Report of all strings set—surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	257'	Common	200	3% CC & 2% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

Depth interval treated

W E L L L O G

State *Geology* *34-24*
WICHITA BRANCH

OPERATOR: McGinness Oil Co. SEP

WELL NAME: # 1 Jindra LOCATION: S/2 SW NW 5-34S-2W

COUNTY: Sumner STATE: Kansas

WELL COMMENCED: 4-8-1982 WELL COMPLETED: 4-20-1982

ELEVATION: _____ TOTAL DEPTH: 4499'

PRODUCTION: D & A RIG NO: 1

Run 6 Jts. of new 8 5/8, # 24, tallied 252', set @ 257'.

CASING - 8 5/8" Cemented w. 200 sx of Common, 3% CC, 2% Gel.

5 1/2" --

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0'	40'	Top Soil	Slope test @ 264'	3/4° off
40'	830'	Shale	" " @ 970'	1° off
830'	1020'	Shale & Sand	" " @ 4212'	1° off
1020'	1860'	Shale		
1860'	4499'	Lime & Shale		

RECEIVED
STATE CORPORATION COMMISSION
MAY - 5 1982
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS

COUNTY OF

The undersigned hereby certifies that to the best of his knowledge