

1/9/11

**CONFIDENTIAL**

**Geological Report**

American Warrior Inc.  
Schneider #1-26  
335' FSL & 335' FWL  
Sec. 26 T 34S R2W  
Sumner County, Kansas

James Dilts  
Geologist

RECEIVED  
JUN 04 2010  
KCC WICHITA

**American Warrior, Inc.**

## General Data

Well Data: American Warrior Inc.  
Schneider #1-26  
SW-SW-SW  
335' FSL & 335' FWL  
Sec. 26 T34S R.2 W.  
Sumner County, Kansas  
API # 15-191-22, 548-0000

Drilling Contractor: Val Drilling Co., Rig #3

Spud Date: 9/17/2008

Rotary TD Date: 9/2016/2008

Rotary TD: 4649'

Elevation: 1104' Ground Level  
1114' Kelly Bushing

Casing: Surface 320' 8 5/8" 23# surface casing set at  
330' w/ 235 sx 60/40 poz 3%cc 2% gel  
Production 4602.76 new 5.5" 15.5# @4614'  
165 sx AA-2

Samples: 10' wet and dry, 500' to RTD

Drilling Time: 500' to RTD

Electric Logs: DIL/CDL//BHCS/CNL

Drillstem Tests: None

Problems: None

**RECEIVED**  
**JUN 04 2010**  
**KCC WICHITA**

## Formation Tops

### Schneider 1-26

Heebner	2570'-1456
Toronto	2657'-1543
Brown Lime	2937'-1823
Kansas City	4388'-3274
Marmaton	3733'-2619
Pawnee	3834'-2720
Ft Scott	3871'-2757
Cherokee	3883'-2769
Mississippi	4148'-3034

93'MW	60%w	40%mud
202'MW	80%w	20%mud

Summary: Due to structural position, the decision was made to case the Schneider #1-26 for further evaluation.

Suggested perforation: Mississippi 4170'-4172'

**RECEIVED**

**JUN 04 2010**

**KCC WICHITA**