

SCOUT TICKET

COUNTY Clark STATE Kansas DATE 6/24/54

COMPANY Pure Oil Company

FARM J C Harper NO. 2

SEC. 2 TWP. 34 RGE. 21 ELEV. 18696DF

Location in Sec.					
Fr. N.	Fr. S.				
Fr. E. <i>SW</i>	Fr. W.				
C of <i>SE NW</i>					

LOS { 1858 DF  
186661

PERFORATIONS	GAS PAYS		16" CASING RECORD
	Hollenberg		13"
	Herington		10% 580(325)
	Padock		8 5/8"
	Krider		7"
	Odel		6"
	Winfield		5 1/2" 5540(250)
	Gage		TD
	U. Ft. Riley		PB
	L. Ft. Riley	Schl	Nat
	L4M	4510 2 <sup>nd</sup> sd 5432	Acid
	M4M	5103 3 <sup>rd</sup> sd 5464	AA
	Chp	5234 Miss 5482	DEL
	Movr	5376 Stagen 5594	Rock
	Movr 1 <sup>st</sup> sd	534 VCT	

Contractor *Wye-Snell*

6/9/54	Location:
JUN 16	✓
JUN 23	M.I.R.T
JUN 30	φ 2327
JUL 7	φ 4031
JUL 14	φ 5356
JUL 21	φ 5390-5428 Rec 32'
	2' L <sub>2</sub> Tan sdy Xlt ul glauc parting
	1' sh BK-grv
	9' ss Fin. brk-grv hard lite
	ul BK carb sh karina
	12' sh dk brk ul sd layers
	6' sd F-M Grv-Tan Siliceous
	Hard lite glauc part adot
	Bleeding loc sh partings
	8' sh BK w gen sd Lam
	hard & lite

AUG 1 1954  
AUG 2 1954  
SEP 2 1954

# 5428-45 Rec 16  
 3' sh Dr GRY thin sd latt.  
 1' sd F. fine glassy w/ thin  
 GCM sh partings  
 1' sd F. latt, w/ pure  
 Grad edar bleeding, as 106  
 am frac  
 6' sd F. hard tile  
 Grad Fluor am frac  
 3' sd F. hard glassy tile  
 Grad Para. edar bleeding  
 G.O.  
 2' sh Dr GRY rather w/ sd latt

DST 5395-5445 2 1/2 hr Gas to  
 1 hr @ 40 min TSTM Rec 180' GCM  
 500 Hvy 0.06 CM 300' SH  
 FP 1180 BHP 2055 (app)

# 5445-91 Rec 43'  
 23 1/2' sh Dr GRY sdy rather  
 w/ interbedded sd crs  
 lony  
 5 1/2' sd Lony f-crs grain  
 Por without pebbles  
 3' sd f-crs Buff NS  
 3' " " White tile  
 Slipers NS of Oil  
 1' " 85 above Tile  
 " 74m Vx Foss  
 3' sh GRY fine pyritic

DST 5473-91 Failed  
 " 5474-95 1 1/2 hr Gas 23 min  
 189 MCF (75) Rec 180' GCM  
 FP 0-185 BHP 1265 (app)

# 5557  
 RID 5720 Schl

DST 5525-5720 Failed  
 " 5524-5720 "

WOLT  
 RUCET 60

(36) 5473 1/2 - 83 1/2  
 5/6 gal sl. oil SW PH for 12 hr  
 Gas TSTM  
 dec 10.4 gal at end of 12 hr  
 A/300 HD

# SCOUT TICKET

COUNTY	Clark	STATE	Kansas	DATE	
COMPANY	Pure Oil Company				
FARM	J & C Harper	NO.	2		
SEC.	2	TWP.	34	RGE.	21 ELEV.
Location in Sec.					
Fr. N.	Fr. S.				
Fr. E.	Fr. W.				
C of NE SW					

PERFORATIONS	GAS PAYS	CASING RECORD
	Hollenberg	13"
	Herington	10 3/4"
	Padock	8 5/8"
	Krider	7"
	Odel	6"
	Winfield	5 1/2"
	Gage	TD
	U. Ft. Riley	PB
	L. Ft. Riley	Nat
		Acid
		AA
		DEL
		Rock

**Contractor**

AUG 1 1951	A/13000
	A/1500 mud
	F/ Diesel 3000 # SD
	CO. h. u. d. oil
AUG 13 1951	F/ 2 B.D. Acid water in 3hr 500 MCF
	SI
	F/ 25 B.D. in 4 hr
	SI for storage
AUG 26 1951	F/ 56 1/2 B.D. in 9 hrs 5/8" ch
	SI 15 hrs
	F/ 59 1/2 B.D. in 8 hrs 1 3/4" ch
	TP 60
	SI 15 hrs TP 800 #
	F/ 56 B.D. in 9 hrs 10/64" ch
	TP 60
	SI 15 hrs
SEP 1 1951	F/ 25 B.D. in 3 hr 1" ch
	F/ 25 B.D. in 4 hrs 1" ch
	SI for storage TP 800 #

SEP-18-1954

F/ 54 B.O. @ No water in 12 hrs.  
3/8" ch TP120

NOT

SEP-29-1954

State Test 186.3 B.O.P.D 3/8" ch  
TP 110"

⊕