

State Kansas County Barber

Company Barbara Oil Co. & Newmont et al. Well No. 1

Farm Holmes "A"

Survey \_\_\_\_\_

Block No. \_\_\_\_\_ Sec. 2 Twp. 34 S Range 13 W

Co-Ord. \_\_\_\_\_ Elev. 1578 DF

NE NW SE

1580 KB


Contract for Barbara Oil Co.  
and Newmont, et al

- 50% Barbara Oil Co.
- 15% Newmont Oil Co.
- 15% Cyprus Oil Co.
- 12.5% Phelps-Dodge Corp.
- 7.5% Pennypacker, et al

5200' Simpson Sd. Test

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 2310 Ft. from S. Line \_\_\_\_\_

Ft. from W. Line 1650 Ft. from E. Line \_\_\_\_\_

Date	Depth	
		N/2 SE/4 PO: from Aylward Drlg. Co. subj. to 1/16 of 7/8 ORRI
		E/2 NE/4 Acreage Cont: Superior Oil Co. subj. to 1/16 of 7/8 ORRI
<u>7-9-57</u>		RURT
<u>7-10-57</u>		Set 246' of 8 5/8" w/175 sx. cement. 2% gel 2% C.C. P.D. 8:00 A.M. (approx.)
<u>7-11-57</u>		SUS

Date	Depth	
7-12-57	1800'	drlg.
7-15-57	2980'	drlg.
7-16-57	3315'	drlg. (1 <sup>1</sup> / <sub>2</sub> <sup>o</sup> off @ 3075' - Bit #5
7-17-57	3662'	drlg. (1 <sup>1</sup> / <sub>2</sub> <sup>o</sup> off @ 3410' - Bit #6
7-18-57	3934'	drlg. (Bit #7 @ 3870' 1 <sup>o</sup> off)
7-19-57	4125'	drlg. (Bit #8)
	3840'	Heebner (-2260)
	4004'	Lansing (-2424) (36' higher than #1 Donovan E) Stn. 4003-06
7-22-57	4510'	Making a Trip.
7-23-57	4649'	Miss. chat (-3069) good show of oil in wet samples, good saturation, good porosity, white chert, fossiliferous & trace of Cowley. (42' higher than #1 Donovan E
	4670'	(calling DST'er)
7-24-57	4649-70	DST #1 op. 25" Cl. 15" Rec. 30' Mud, w/a few spots of oil BHP-0 FP 0-0#
DST #2	4651-4700	op. 1 hr. strong blow through, rec. 720' gas, 20' mud BHP 275# FP 55-65# Hydro Head 2555



Date	Depth	
		sd. w/odor, stain, & sat. Fl-
		uorescent light showed spotted
		fluor.
	5153'	drlg. - to log & run DST
7-30-57		DST #3 5092-5106 straddle
		packers. op. 1 hr. fair blow
		Rec. 220' gas 450' SW BHP
		1935# IBHP 1875# SI/20" FP 97.
		318# Hydro. head 2695
	5164'	R.T.D. D & A
		Plugging completed 4:00 P. M.
		7-30-57