

15-025-21196

14-34s-21w

NATURAL GAS ANALYSIS REPORT

Sampled by:
Trilobite Testing, L. L. C.
Hays, Kansas
Scott City, Kansas
Phone: 800-728-5369
Fax: 913-625-5620

Analyzed by:
Caraway Analytical, Inc
P. O. Box 2137
Liberal, Kansas 67905
Phone: 316-624-5389
Fax: 316-626-7108

Lab Number:	996331	Analyzed:	12/13/99
Sample From:	Bouziden 1-14 DST 2	Pressure:	
Producer:	Zinke & Trumbo	Temperature:	
Date:		Location:	14-34-21
Time:		County:	Clark
Sampler:		State:	Kansas
Source:		Formation:	L Morrow

	Mole %	GPM
Helium	He: 0.141	0.000
Hydrogen	H2: 0.001	0.000
Oxygen	O2: 0.000	0.000
Nitrogen	N2: 2.769	0.000
Carbon Dioxide	CO2: 0.164	0.000
Methane	C1: 91.328	0.000
Ethane	C2: 3.065	0.820
Propane	C3: 1.270	0.350
Iso Butane	iC4: 0.176	0.058
Normal Butane	nC4: 0.438	0.138
Iso Pentane	iC5: 0.117	0.043
Normal Pentane	nC5: 0.139	0.050
Hexanes Plus	C6+: 0.392	0.171
TOTAL:		100.000 1.630
Z Fact:		0.9977
SP.GR.:		0.6195
BTU (SAT):		1045.3 @ 14.73 psia
BTU (DRY):		1063.8 @ 14.73 psia
OCTANE RATING:		123.9

COMMENTS:

0.000