

4
Hayden Ranch

State Kansas County Clarke

Company Pure Oil Co.

Farm K. C. Harper Well No. 2

Sec. 11 Twp. 34S Range 21W

fr N fr E fr S fr W

of C NE NW

Contractor _____

Remarks _____

Comm. 6-30-55 Comp. 9-7-55

Elev. 1897 T. D. 5560 P. B. 5511

Pay 5472-96

38° 6E.

I. P. 2201 BOPO R. P. _____

Casing Record: 13 3/8 7

20 10 3/4 5 1/2 5523/325

16 82/115 95/8 565/300

	RURT/	Tops	
7-13	2820		<u>Samps</u> <u>Analysis Aug 19/10</u>
JUL 20 1955	<u>04999</u>		<u>Schl. by Co.</u>
JUL 27 1955	<u>5432-57</u> <u>rev 25'</u>		<u>Long - KS 4543</u>
	<u>5457-80</u> <u>rev 23'</u>		<u>Murm. 5124</u>
	<u>now reaming</u>		<u>cek 5303</u>
AUG 3 1955	<u>5432-57</u> <u>rev 25'</u>		<u>Murm sh. 5421</u>
	<u>3 1/2' ls. hd drs</u>		<u>2nd sd. 5471</u>
	<u>4 1/2' sh drk gry</u>		<u>Muss 5544</u>
	<u>9' sd. fm gn. hd tite w/ sh stks</u>		
	<u>6 1/2' interbedded sd & sh.</u>		
	<u>1 1/2' sh drk gysht.</u>		
	<u>5457-80</u> <u>rev 23'</u>		
	<u>2 1/2' sh. drk gry</u>		
	<u>11 1/2' sd fm gn. hd tite to sh ipon bleeding org</u>		
	<u>9' sd fm - md gn. brn, gravel fm & spec</u>		
	<u>gd str.</u>		

45480-96 rec 16'
3' sd fm 2nd gr. tite to 9d pr, 9d str,
odor & flavor, bleeding 0 & 9
2' sd w/ hd tite, bleeding 0 & 9
11' sh. drk grey sand

45516-34 rec 18'
2' sd fm 9d tite w/sh lam.
16' sh.

RTD 5560 ^{run} Schl. 5 1/2 @ 5523/
AUG 1 0 1955 325

PR to 5511 p 96/5472-96
swab land & planned 14060 in 4 1/2 hrs.
then 2 1/2" tbg, planned 67460 in 13 hrs,
then 3" ck. FTP 175
8

SI WOT

AUG 1 7 1955

AUG 2 4 1955 planned 366 BO in 11 hrs.

29/64 "ck TP 240, CP 150

26/64 "ck. Potential 2201 BOPD
TP 240 CP 150

37° Gtg

AUG 3 1 1955

SEP 7 1955

stake potential

2201 BOPD - Bottom hole bomb
flo test 97 BO 3 hrs. 27/64 "ck.
TP 330 CP 160 38° GR.

4