

State

KANSAS

Field

Harpur Ranch

County

CLARK

Company

Pure Oil Co.

Farm

J. C. HARPER "B"

Well No.

1

Sec.

14

Twp.
Blk.

345

Range
Survey

21W

fr N

fr E

fr S

fr W

of

C SWNE

Contractor

Unit Merg. Co.

Remarks

Comm.

3-20-55

Comp.

8-3-55

Elev.

1824

T. D.

5535

P. B.

Pay

I. P.

D & A

R. P.

Casing Record:

13 3/8

7

20

10 3/4

580/250

51 1/2

5527/300

16

80/250

85/8

Casing Record by Co.

Tops

2195

MAR 30 1955

Ø 228

Ø 2787 making trip

Lung KC 4489

APR 6 1955

Ø 4868

Mora 5374

APR 13 1955

Ø 5380 - 5404 rec 24'

MISS 5510

1' 1/2. dk grey drs pyrite

Schl. by Co.

3' sh grey grn cotton

Lung KC 4487

1' 1/2. tan - grey hd foss.

Mora fm 5372

3' sh. grey grn cotton

Mora sd 5406

6' 1/2. tan - grey hd. foss

" " 5436

10' sh yellow fm to grey cotton

Mora sd 5473

Ø 5404 - 54 rec 50 MISS 5510

2' sh grey w/ thin ls. laminae

17' sd. fm hd f. the glauc occasional

thin for stks bleaching o & g

8' sh. Cr K grey soft

13' sd. fm hd f. the lung pyrite

shaly, bleaching o & g in part

4' sd w/strk of gd por glauc bleeding
089.

6' sd fm. gd por lt. str, odor of fluor

DST 5408-54 on 45 min. gd blo
dried in 15 min. (Bry passed thro)
rec 750' slt. gcm FP 252-429
BN 1618/15

\$5454-80 rec 26'

2' ss. fm grain fm por & perm. lt. str
& fluor
1 1/2' ss fm to the slt. purple fm. odor

13' sh dk grey

2' imbedded slt & sh.

5 1/2' ss fm to md grained lt. str
& fluor gd odor

1 1/2' sd as above cgl.

\$5480-91 rec 10'

3' sd fm to md gm glauc cgl. ns.

4' cgl ns.

rearing corals

RTD 5535 Jan 5 Schl

DST 5452-5535 on 1 hr. rec 180'
Mud, 1105' MSW FP 100-351 BN 1960/15

5 1/2' @ 5527/300

CO & P 96/5429-53
WOCT

27 Apr. RUCT CO to? 300 mud out from 50/120,000
fracs would not take prep to reverse
out frac

Oil Co.

State _____
County _____
Company _____
Farm _____
Sec. _____ Twp. _____ Range _____ Well No. _____
Blk. _____ Survey _____
fr N _____ fr E _____ fr S _____ fr W _____
of _____
Contractor _____
Remarks _____
Comm. _____ Comp. _____
Elev. _____ T. D. _____ P. B. _____
Pay _____

I. P. _____ R. P. _____
Casing Record: 13 3/8 _____ 7 _____
20 _____ 10 3/4 _____ 5 1/2 _____
16 _____ 8 5/8 _____

		Tops
	4 May	
	Still swabbing on road	
MAY 11 1955	✓	
MAY 18 1955	re frac (100,000 #456?)	
MAY 25 1955	frac 30,000 3d / 65,000	
	pumping swabbing road	
JUN 1 1955	✓ Still swabbing road and	
JUN 8 1955	✓	
JUN 16 1955	✓	
JUN 22 1955	✓	
JUN 29 1955	✓	
JUL 6 1955	✓	
JUL 13 1955		
JUL 20 1955	sy pump w/ 50 sk (5429-53)	
	CO to 5484	

P10/5448-53, 10/5435-40

A
500 mm Swallowed 72661s load, 8/20661s sw
Swallow 72661s sw in 20 hrs.

JUL 27 1955 A P1/5435, 1/5440

Agonized & unbr. ant. & face.
59/5450, 1/5456 planned 260 in 1 hr.

Swallow 9460^{load} & 1946w, 5/15g, still
swallowing load

AUG 3 1955

D & A

¢