

CHARTER PRODUCTION COMPANY
224 East Douglas, Suite 400
Wichita, KS 67202

HARDEN FARMS #1-3

NE SW SW Section 3-T34S-R25W

Clark County, Kansas

GL 2057

KB 2070

SAMPLE TOPS:

Heebner 4258' (-2188)

Lansing 4438' (-2368)

Swope 4968' (-2898)

Hertha 5018' (-2948)

Marmaton 5072' (-3002)

Cherokee 5226' (-3156)

DST #1 5440-5525' 30/60/90/120 GTS/1" into first shutin. 2nd open
27 MCF increasing to 73 MCF Rec. 250' GCM IFP: 108-113 ISIP: 1920
FFP: 129-176 FSIP: 2038

DST #2 5560-5605' 30/60/60/60 1st open, fair blow increasing to strong
blow. 2nd open, strong blow in 10" Rec. 20' mud. IFP: 55-44 ISIP: 333
FFP: 44-33 FSIP: 838