


State KANSAS Field McKinney
 Company Graham-Michaelis County Clark
 Farm Theis "B" No. 1
 Sec. 7 Twp. 34 Range 25

Spot C W 1/2

Contractor Co tools

Remarks



Comm. 9/28/56 Comp. 1-13-57

Elev. DF 2215 GL 2200 KB TD 5895 PB

Pay 5736-40, Mor

5748-61 - ~~5779-5802~~ charter

I.P. ^{st del.} 826 MCF Press. BP 1510

Casing Record: 13 3/8" 7"

20" 10 3/4" 5 1/2" 5895/?

16" 8 5/8" 1149/500

	Sample	Log
3671		
OCT 24	Mar 4929	Mar sh 5702
Dst 5700-90 op 1 hr g 270 MCF Jan 46 11		sd 576
Rec 300' sh 9' DC M	MOR 5700	charter 5741
FFP 230-230 BHP 1035/30	char 5749	
DST 5812-80 op 30 min rec		
65' 3/4 9 CM, No pressures		
man log RTD 5800		
102.0 C		
102.0 C		
OCT 31		
NOV 7		
RTD 5895 man log		
PF 32/5836-44 A/500 mud		
Fr/2000 sd/1000, g 2,500 MCF		
pl @ 5823 PF 24/5810-16		
80/5786-5806 16/5778-82		
A/1000 mud summary g 2,500 MCF		
Fr/2000 sd/4000. dr pl num. 2" T		
NOV 14		
g 2,300 MCF, A/4000 7 1/2% g 2,500 MCF		
59/250, WOC CO		
NOV 21		
PF 92/5779-5802, A/500 m g 200 MCF,		
A/1000 m g 500 MCF A/Fr 2000, 1,500 MCF		
Prep to fr.		

NOV 27 Fr/8000 sd/4000, ~~fr/3000 sd/1500~~,
A/2000 7½% q 2,500 MCF, A/8000 7½%
q 3,089 MCF, set pl @ 5772, Pf 12/5758-61
A/500 m, fr/3000 sd/0 A/1000 7½% q 2,500 MCF
Ø pl q 5,000 MCF, set pl @ 5740 Pf 12/5736-80
A/500 m q 1,909 MCF prep to fr

DEC Fr/3000, sd/1500 A/500 7½% Swab, q
1,600 MCF A/2000 7½% Ø all plugs q 6,000 MCF.
run 2½" T ~~W.O.T.~~

DEC 12 ✓ FEB 13 st Del. 820 MCF
R.P 1510

DEC 19 ✓

JAN 3 ✓

JAN 9 ✓

JAN 16 ✓

JAN 23 ✓

JAN 30 ✓

FEB 6 ✓

