


State Ks. Field McKINNEY
Company ATLANTIC County CLARK
Farm FRAME G.U. No. 1
Sec. 15 Twp. 34 Range 25

Spot CSW

Contractor REAVES

Remarks shallow 25% P.D. 5800'



Comm. 5-28-58 Comp. 7-23-58

Elev. DF 2063 GL 2056 KB 2065 TD 5800 PB 5766

Pay 5666-70, 70-72, 72-83, 5708-12, 12-14, 14-20
5750-51, 52-54

COF I.P. 6,020 mcf S.I. 1739 Press.

Casing Record: 13 3/8 7"

20" 10 3/4 5 1/2" 5800/200

16" 8 5/8 1206/600

<u>RUR</u>	Sample	Log
JUN 4 <u>spud, cas</u>		HB 4290
<u>62194</u>		LAN 4478
JUN 11 <u>63977</u>		HARM 5150
JUN 18 <u>65444</u>		CHERO 5351
JUN 25 <u>DST 5611-70</u>		MOR 5600
<u>sp. 1' w/blk T.O.</u>		CHES 5612
<u>Rec 30' mud</u>		
<u>EP 15-35</u>		
<u>SIP 513/30"</u>		
<u>DST 5663-5730 fail</u>		
<u>RTD 5800, log</u>		
<u>DST 5648-5800</u>		
<u>sp. 1' gts 17"</u>		
<u>9: 62 mcf - 20"</u>		
<u>stab, Rec 65'</u>		
<u>SGCM, EP 30-40</u>		
<u>BHP 1910/30"</u>		
<u>SD. - 400.</u>		

JUL 2 CSG WOC JUL 9 CSG MICT
CO, 5766
P/68 5666-83
78 5708-20
34 5750-56, Ac 100 (7 1/2%) +
20# sd (WG-3)

... 1 Hbg w/ Ref. 5618, from 4240 Kers
no sd, fm. didn't brk
pull Hbg CO. 5756

P/8 5752 - 54
8 5712 - 14
8 5670 - 72, 4 B.D. 83 MCF
 $\frac{1}{4}$ " ck

P/8 5750 - 51
24 5714 - 20
16 5708 - 12, 3 B.D. 90 MCF - $\frac{1}{4}$ " ck
FCP-64

P/44 5672 - 83
16 5666 - 70 10 B.D. 135 MCF - $\frac{1}{4}$ " ck
FCP-95, Ac 4375 (72%)
fuc 20x20, Surd, 2 B.D. 3.5 A.
FTP-560, FCP-900, totg

2-16 prop test
JUL 23

COE 6,020 MCF
SIP - 1739